



**SAN BERNARDINO COUNTY
SOLID WASTE MANAGEMENT DIVISION**
222 West Hospitality Lane, 2nd Floor
San Bernardino, CA 92415-0017
Fax: 909-386-8900

ADDENDUM NO. 3

**TO THE PLANS AND BID DOCUMENTS FOR THE PHASE 1B LINER
CONSTRUCTION PROJECT
at the LANDERS SANITARY LANDFILL
in Landers, California**

January 28, 2026

~~BID OPEN: 10:00 A.M. February 3, 2026~~

BID OPEN: 10:00 A.M. February 5, 2026

The following changes and/or additions shall be made to the Plans and Bid Documents for the Phase 1B Liner Construction Project at the Landers Sanitary Landfill. All other requirements of the Plans and Bid Documents shall remain the same.

The following changes shall be made part of the Contract Documents, and the Bidder should acknowledge receipt thereof on the Bid Proposal.

I. PROJECT TECHNICAL SPECIFICATIONS REVISIONS

1. Section 2C – Earthwork, Subsection 3.3 – General – G, Paragraph 1 of the Technical Specifications, delete and replace with the following:

“The minimum in-place compaction for all fill materials except for the screened 1-inch minus material Layer, stockpile materials, and the Protective Soil Cover Layer shall be 90 percent of the maximum dry density as determined by ASTM D 1557. The moisture content of compacted unclassified fill shall be at ± 2 percent of optimum moisture content for the specified material.

The minimum in-place compaction for Northwest Stockpile fill material shall be 85 percent of the maximum dry density as determined by ASTM D 1557 for the outer slopes (10' or equipment width). The moisture content of compacted fill for

the outer slopes shall be at ± 3 percent of optimum moisture content for the Northwest Stockpile fill material. There is no compaction requirement for the internal fill material of the Northwest Stockpile nor the Southeast Rock Stockpile fill material.”

2. Section 2C – Earthwork, Subsection 3.12 – Veneer Fill, Paragraph 2 of the Technical Specifications, delete and replace with the following:

“Veneer Fill Material screened from the Unclassified Excavation as shown on Plans, or as otherwise designated by the Engineer, shall be used for veneer fills, in accordance with the requirements of Section 2.7, above. The Veneer Fill material shall be transported to the cell area where required and spread to a depth ranging from 1-inch to 6-inches and proof rolled with a steel drum roller weighing not less than 200 pounds per linear inch of drum width or approved equivalent method.”

II. PROJECT QUESTIONS AND ANSWERS

1. Due to other conflicting contracts bidding the week of February 2nd, please consider a two (2) week extension to the bid date of February 3rd. Additionally, this will allow for subcontractor and supplier coordination insuring the most economical pricing for the public. This would benefit SBCEPW at this juncture to provide more time for the compilation of pricing for this project.

A1. The Bid Open date for this project has been extended to 10:00 A.M. February 5th, 2026. No further extensions are anticipated at this time.

2. Can the CARB certificates and the List of Subcontractors Form (page 40-41) be submitted after the bid opening? Public Agencies have provided up to 10 days after the bid due date to submit CARB certificates for listed subcontractors.

A2. CARB – Contractor Certification Form and CARB – List of Subcontractors Form must be completed and submitted with bid by the Bid Opening. If not completed and submitted with bid, bid will be declared nonresponsive.

3. Please provide the List of Subcontractors Form (page 40-41) in landscape to fill printing page for better coverage.

A3. If Pages 40 & 41 of the yellow pages do not print correctly in Landscape, please refer to Attachment 1 in Addendum No. 3 for a portrait orientation with the content rotated to 90 degrees. Otherwise, please use the documents as provided.

4. Please provide the location of the offsite water source. Will this source be shared with the ongoing landfill operations?

A4. Contractor is responsible for determining location of offsite water source. Ongoing landfill operations actively use a water source located on the southwest

corner of Landers Lane and Reche Road. Please refer to Section 2B – Construction Support Tasks, Subsection 1.8 – Construction Water.

5. For Bid Items 6 and 7 is there a compaction spec on the placement of material in the stockpiles? Based on experience and the information in Appendix D - Field Exploration, this material is very hard and rocky which may require different compaction methods and hauling units depending on the nature of the cut.

A5. *Please refer to Section 2C – Earthwork, Subsection 3.3 – General – G and the Project Technical Specification Revisions No. 1 attached in this Addendum No. 3.*

6. For Bid Item 9, where do you anticipate finding the 3" minus in excavation as Appendix D - Field Exploration indicates very hard rocky and hard materials to be expected? If 3" minus is not found will this be required to be screened?

A6. *Material suitable for the construction of Unclassified Fill is anticipated to be obtained from the Unclassified Excavation area per the grades shown on Sheet 4 of the Construction Drawings and select grading will be required. Per Section 2C – Earthwork, Subsection 3.6 – Unclassified Fill of the Technical Specifications, screening of native materials may be required to meet the maximum particle size requirements.*

7. What materials are to be used for Bid Item 11? Will this be from the screened pile?

A7. *Please refer to Section 2C – Earthwork, Subsection 2.7 – Veneer Fill Material of the Technical Specifications for the Veneer Fill Material source information.*

8. Where is the Low Permeable material on site located?

A8. *There is no Low Permeable material required for this project. Please refer to Section 2C – Earthwork, Subsection 3.12 – Veneer Fill and the Project Technical Specifications Revisions No. 2 attached in this Addendum No. 3.*

9. Is there a rock ripping standard spec for this project? During excavation what is the criteria/requirements for blasting to be initiated?

A9. *A rock ripping standard specification (production rate) has not been established to initiate blasting. Please refer to Section 2C – Earthwork, Subsection 4.13 – Basting – Item No. 70 as Contractors are reminded of the incentive payment adjustment in the Example Calculation (for reference only). Per the Bid Schedule Item No. 70, no additional payment will be made for quantities over 350,000 cubic yards listed on the Bid Schedule.*

The Contractor will encounter rock of varying degrees of hardness during the excavation and grading work. Information made available on the excavation area

has been provided in Appendix D – Field Exploration of the Technical Specifications. The Contractor shall be entirely responsible for any cost resulting from wear, damage, or maintenance of construction equipment.

- 10.** Please confirm the required dollar amount for the Builder's Risk coverage outlined in the Standard Contract, Section 5.3.2, Subsection F.

A10. *Course of Construction/Installation (Builder's Risk) Property Insurance will be defined in Addendum No. 4, which shall be issued at a later date.*

If you have any questions, please contact Joshua LeRoy at (909) 386-8629 or you may contact me at (909) 386-9017.



Johnny Gayman, P.E.
Chief Engineer

01/28/2026

Date

ATTACHMENT NO. 1

CARB List of Subcontractors Form

(Pages 40 & 41 of Yellow Pages)

LIST OF SUBCONTRACTORS FORM

In compliance with the Subletting and Subcontracting Fair Practices Act of the Public Contract Code of the State of California, each bidder shall set forth below: (a) the name, contractor's license number and the location of the place of business of and (b) the portion of the work which will be done by each subcontractor who will perform work or labor or render service to the Contractor in or about the construction of the work in an amount in excess of one-half of one percent (1/2%) of the Contractor's Total Bid Price. Notwithstanding the foregoing, if the work involves streets and highways, then the Contractor shall list each subcontractor who will perform work or labor or render service to Contractor in or about the work in an amount in excess of one-half of one percent (1/2%) of the Contractor's Total Bid Price or \$10,000, whichever is greater. The District may, within its sole discretion, grant additional time to provide the below requested information.

If no subcontractor is specified for a portion of the Work, or if more than one subcontractor is specified for the same portion of Work, to be performed under the Contract in excess of one-half of one percent (1/2%) of the Contractor's Total Bid Price or \$10,000, whichever is greater, or if the work involves streets or highways, then the Contractor shall be deemed to have agreed that it is fully qualified to perform that Work, and that it shall perform that portion itself.

Portion of Work	Subcontractor	Location of Business	License Number	DIR Registration No.	CARB Certificate of Compliance No.

Portion of Work	Subcontractor	Location of Business	License Number	DIR Registration No.	CARB Certificate of Compliance No.

Name of Bidder _____

Signature _____

Name and Title _____

Dated _____

END OF LIST OF SUBCONTRACTORS FORM