

ADDENDUM NO. 6  
TO THE BID DOCUMENTS FOR THE  
CHINO AIRPORT PERIMETER FENCE REPLACEMENT PROJECT

The following changes and/or additions shall be made to the plans and/or specifications. All other requirements of the contract documents shall remain the same. The Bidder shall acknowledge receipt of the addendum by inserting its number and date in the Bid Proposal.

**Questions/RFIs:**

Questions/RFIs deadline has passed. No additional questions/RFIs will be accepted.

**Question and Answers:**

Q: There is a requirement to register with ePro but there's also an option to mail in the bid packet w/ bid bond. Can the mail bid response support a valid bid response on its own without submitting through ePro?

A: Mailed in bid packages are accepted. See Instruction to Bidders, Section E of the bid documents.

Q: Addendum #5 now has 8' Ameristar Montage II w/ Invincible pickets. The drawing shows a 4-rail system. Is this system to be 3 or 4 rails?

A: System to be 4 rails.

Q: DSA certified Class 1 inspections and surveying for fence line/sign monuments have been called out but there is no mention of grounding for the fence. Is grounding required on the fence/gate system? Is there a requirement for NETA testing of said grounding?

A: This project does not require a DSA certified inspection and General Note 19 can be disregarded.

Q: Can you provide the footing dimensions for the pilasters and 1,800'LF concrete curb that the existing chain link fence is embedded in along Merrill Ave that need to be demolished and graded?

A: Information on the existing pilaster or curb at the existing fence along Merrill Avenue is not available.


Q: Please confirm that the Fortress V3 'CT4' is equivalent to the Montage II 4-rail. See attached for specs and drawings.

A: Fortress V3 'CT4' is equivalent to the Montage 2 4-rail.

Q: Please find our two options for material substitute request attached. Option 1 more closely matches the Ameristar design, but at a lower cost to the customer. Option 2 is very similar to Option 1, but is a little easier to manufacture, resulting in additional savings to the customer.

Option 1 – Capital Steel Product- Top Guard – Picket Center Weld  
Option 2 – Capital Steel Product- Top Guard – Picket Face Weld

A: Option 1 with the picket center welded is an acceptable substitution, as long as, it complies with the ASTM standard requirements listed on sheet G0.12 under the specification section 32 31 19 - FENCES AND GATES - ORNAMENTAL METAL.



Don Day, Director  
Project and Facilities Management Department

DD:mv

San Bernardino County  
Project and Facilities Management Department  
385 North Arrowhead Avenue, Third Floor  
San Bernardino, CA 92415-0184  
<https://pfm.sbcounty.gov/>

DATE: September 18, 2023