

**REPORT OF PERCOLATION FEASIBILITY STUDY  
PROPOSED ONSITE WASTEWATER TREATMENT SYSTEM  
80526 AMBOY ROAD  
CITY OF TWENTYNINE PALMS  
SAN BERNARDINO COUNTY, CA 92277**

PROJECT NO.: 904-13  
REPORT NO.: 1

MARCH 15, 2024

SUBMITTED TO:

**DEPARTMENT OF PUBLIC WORKS, SPECIAL DISTRICTS  
222 W. HOSPITALITY LANE, 2<sup>nd</sup> FLOOR  
SAN BERNARDINO, CA 92415**

PREPARED BY:

**HILLTOP GEOTECHNICAL, INC.  
786 SOUTH GIFFORD AVENUE  
SAN BERNARDINO, CA 92408**



**HILLTOP GEOTECHNICAL**

INCORPORATED

March 15, 2024

786 S. GIFFORD AVENUE • SAN BERNARDINO • CA 92408  
Phone 909-890-9079 • FAX 909-890-9055  
hilltopg@hgeotech.com

**Department of Public Works, Special Districts**

Attn: Mr. Alfonso Fausto  
222 W. Hospitality Lane, 2<sup>nd</sup> Floor  
San Bernardino, CA 92415

Project No.: 904-13

Report No.: 1

Subject: **Report of Percolation Feasibility Study, Proposed Onsite Wastewater Treatment Systems, 80526 Amboy Road, City of Twentynine Palms, San Bernardino County, CA 92277.**

- References:
1. **San Bernardino County Public Health Environmental Health Services, *Percolation Testing and Reporting Standards for Onsite Wastewater Treatment Systems, Revised September 2019.***
  2. **BOA Architecture, *Wonder Valley Community Center Renovation, 80526-1/2 Amboy Road, Twentynine Palms, CA 92277. 02/08/2024.***

Mr. Fausto:


In accordance with your request, we have completed the percolation feasibility study including seepage pit percolation testing in the vicinity of the proposed new septic system to accommodate the proposed community center renovation at the subject site. This testing was performed in general accordance with the Percolation Testing and Reporting Standards for Onsite Wastewater Treatment Systems (OWTS) (revised September 2019) issued by the San Bernardino County Department of Environmental Health (DEHS). A percolation feasibility report is included herein and follows the general format of the San Bernardino County Department of Health Services for percolation testing.

The percolation feasibility study indicates that the proposed OWTS at the subject

site is feasible from a geotechnical engineering viewpoint provided recommendations presented herein are incorporated into project design and implemented during the project construction.

We appreciate the opportunity to be of service on this project. If you have any questions, please call this office at your convenience.

Respectfully submitted,  
**HILLTOP GEOTECHNICAL, INC.**



S. Mack Chen, P.E. C76834, C.E.G. 2688  
Principal Engineer/Geologist

Distribution: (1) Addressee  
pdf Copy Via E-Mail  
Mr. Alfonso Fausto ([Alfonso.fausto@sdd.sbcounty.gov](mailto:Alfonso.fausto@sdd.sbcounty.gov))

NOT FOR

## TABLE OF CONTENT

<b>1.0</b>	<b>DESCRIPTION OF SITE</b> .....	1
1.	Date/Individual that was notified of testing.....	1
2.	Prepared For .....	1
3.	Location of Land .....	1
4.	Proposed Development .....	1
5.	Description of Site and Surroundings.....	1
<b>2.0</b>	<b>EQUIPMENT</b> .....	2
2.1	Equipment.....	2
<b>3.0</b>	<b>METHODOLOGY AND PROCEDURES</b> .....	2
3.1	Location of Exploratory Borings and Percolation Tests.....	2
3.2	Soil Characteristics of the Subject Site.....	3
3.3	Number of Exploratory Borings .....	3
3.3.1	Boring Results.....	3
3.4	Minimum Number of Tests for Seepage Pits.....	4
3.4.1	Percolation Testing Procedures .....	4
3.4.2	Pre-Soak .....	5
3.4.3	Percolation Test Results .....	5
<b>4.0</b>	<b>DISCUSSION OF RESULTS</b> .....	6
4.1	Uniformity of Soil.....	6
4.2	Sources of Variability or Error .....	6
4.3	Interpretation of Results .....	6
<b>5.0</b>	<b>DESIGN</b> .....	6
5.1	General Criteria.....	6
5.2	Conversion of Percolation Rate to Seepage Pit Design Rates.....	7
	<b>CLOSURE</b> .....	8
<b>APPENDIX A</b>		
	PLATE NO. 1	Seepage Pit Test Location Plan
	PLATE NO. 1a	Floor Plans
	PLATE NO. 1b	OWTS Fixture Unit Worksheet
	PLATE NO. 2	Subsurface Exploration Legend
	PLATE NOS. 3 and 4	Exploratory Boring Logs
	PLATE NOS. 5 and 6	Seepage Pit Percolation Test Results
<b>APPENDIX B</b>		
	Commercial Onsite Wastewater Treatment System (OWTS) Certification	

**REPORT OF PERCOLATION FEASIBILITY STUDY  
PROPOSED OWTS  
80526 AMBOY ROAD  
CITY OF TWENTYNINE PALMS  
SAN BERNARDINO COUNTY, CA 92277**

**1.0 DESCRIPTION OF SITE**

**1.1 Date/Individual that was notified of testing:**

A percolation test notification form was filled out and submitted to the County of San Bernardino Department of Public Health (DEHS) prior to percolation testing. Seepage pit drilling was conducted on February 15, 2024, and Pre-soaking and percolation testing was performed on February 16 and 19, 2024.

**1.2 Prepared for:**

This report was prepared for Department of Public Works, Special Districts, 222 W. Hospitality Lane, 2<sup>nd</sup> Floor, San Bernardino, CA 92415.

**1.3 Location of Land:**


80526 Amboy Road, City of Twentynine Palms. A site location map, Figure No. 1, is attached for reference.

**1.4 Proposed Development:**

- a) Type of Project: proposed community center renovation.
- b) Acreage: The subject site consists of approximately 10 acres.
- c) Type of Disposal: The subsurface sewage disposal systems proposed for use on the site consist of one existing conventional septic tank connected to a seepage pit and one new conventional septic tank connected to a seepage pit.
- d) Grading: No grading is anticipated at the proposed OWTS area.

**1.5 Description of Site and Surroundings:**

- a) Topography: The project area was located on a relatively flat area. The project site has an approximate slope of less than 2% sloping down to the south.
- b) Watercourses: No stream courses are located within 200 feet of the



Source: Copied from USGS Topo Map- Valley Mountain Quadrangle 2015



<b>SITE LOCATION MAP</b>	
80256 Amboy Road, Twentynine Palms, CA 92277	
By: MC	Date: 03/2024
Project No.: 0904-13.1	<b>Figure 1</b>

proposed OWTS.

- c) Vegetation: Currently the site contains no vegetation within the location of the proposed septic system.
- d) Existing structures: an existing community center, firehouse, and sheds, etc. are located on the subject site.
- e) Wells: water wells were observed on the site not within 150 feet from the proposed OWTS.
- f) Rock Outcroppings: No rock outcroppings were observed on the site.
- g) Depth to historic groundwater: Borings were drilled on-site, to a maximum depth of 40 feet and showed no evidence of groundwater.
- h) Any other feature that may affect sewage disposal: none.

## **2.0 EQUIPMENT**

### **2.1 The following equipment was used during our percolation testing study:**

- a) Truck mounted drill rig with an 8-inch-diameter hollow stem auger.
- b) 3" diameter hose.
- c) Water indicator.
- d) 3" perforated casing.
- e) Pipe guard (casing sleeve).
- f) Watch / data sheets.

## **3.0 METHODOLOGY AND PROCEDURES**

### **3.1 Location of Exploratory Borings and Percolation Tests:**

The two 8-inch borings were drilled where the proposed septic system will be located. One borehole was drilled to 40 feet below the ground surface (bgs). No groundwater was encountered. The deeper boring was backfilled to 30 feet bgs. The other borehole was drilled to 30 feet bgs. Two boreholes were logged and converted to percolation test pits as part of this study. The approximate test boring locations are shown on Plate No. 1, 'Test Pit Locations and OWTS Layout'.

### **3.2 Soil Characteristics of the Subject Site:**

- a) The soil characteristics for the subject site are considered favorable.

- b) There was no visible evidence of shallow groundwater or impervious bedrock materials in the borings or on site.
- c) Tests and borings performed were consistent with the visual evidence.
- d) The gradient of the proposed seepage pit area is relatively flat.

### **3.3 Number of Exploratory Borings:**

Two borings were drilled on January 16, 2024. The minimum number of exploratory borings required by San Bernardino County DEHS for favorable to moderate soil characteristics of a commercial lot is one (1) boring. One deep exploratory boring was conducted on January 16, 2024.

**3.3.1 Boring Results:** Earth materials underlying the proposed sewage disposal area consisted of alluvium. The alluvial materials consisted of light yellowish brown silty sand. The earth materials were moist and loose to medium dense in consistency.

- a) Soil profile descriptions for the exploratory borings are shown on the boring logs, Plate Nos. 3 and 4.
- b) No low permeability layers were observed in both soil boreholes and soils were generally consistent between both soil borings.
- c) The soils encountered in the exploratory borings were classified by the Unified Soil Classification System (ASTM D2487).
- d) All colors described were moist soil colors. There was no reduction-oxidation mottling observed in either of the exploratory borings.
- e) In the zone of the proposed seepage pit, there was no significant root observed.
- f) Soils associated with the alluvial materials were generally medium dense in consistency.

- g) All observed soils were moist. There were no wet or saturated soils encountered in the subsurface exploration or test boreholes.
- h) No groundwater was encountered on the site.
- i) The test borings were backfilled with minimal compactive effort using excavated soils.

### **3.4 Minimum Number of Tests for Seepage Pits:**

A commercial lot with anticipated favorable soil conditions requires a minimum of two percolation tests. Two percolation tests were conducted on the subject site within the anticipated area of the proposed subsurface sewage disposal system as part of this study.

#### 3.4.1 Percolation Testing Procedures:

##### Excavation of Test Borings

Exploratory boring SP-1 was drilled to a depth of 40 feet for groundwater verification and the other boring SP-2 was drilled to a depth of 30 feet. On January 16, 2024, after the verification of groundwater, boring SP-1 was backfilled to 30 feet. Both boreholes were converted to percolation test holes.

##### Test Holes

- a) Test Hole Diameters: The diameters of the test holes were 8 inches.
- b) Depth of test holes: After completion of the borings, 3"-diameter plastic PVC perforated casing with a nylon sleeve was inserted inside of the auger. The augers were then removed gently; and the bottom was covered with approximately 1 foot of gravel. The remainder of the augers were then removed. Pre-soaking was then conducted on two test holes on January 16, 2024. The drilled depths can be found on the boring logs Plate Nos. 3 and 4.

### 3.4.2 Pre-Soak

- a) Soaking Period: two test holes were pre-soaked on January 16, 2024. Since the water seeps no faster than half the initial wetted depth in 30 minutes. Since January 17 and 18, 2024 were weekend, test holes were re-soaked on January 19, 2024.
- b) Soaking Method: after the insertion of the 3-inch PVC perforated casing, each test pit was filled to the ground surface with water from a truck-mounted water tank.
- d) The percolation testing was conducted January 20, 2024.

#### Measurement of the Percolation Rate:

- 1) Water level in each test hole was filled approximately to the ground surface in each borehole between each 30-minute interval per the DEHS Perc testing manual.
- 2) After setting the water level, the level was allowed to drop every 30 minutes for a total of a 6-hour period. The water level was read with a water indicator from the ground surface. The depths of the borings were recorded with each reading and read with the water indicator. Each reading was recorded on the percolation data sheet.

### 3.4.3 Percolation Test Results

Detailed percolation test results, in general accordance with San Bernardino County DEHS specification, are included in Appendix 'A' as Plate Nos. 5 and 6. The following are tabulated results of the percolation testing:

Gallons of seepage (Q) were calculated from the following equation:

$$Q = \frac{(d_f - d_i) * D * 9}{(d_b - (d_i + d_f) * 0.5) * t}$$

Where

$d_f$  – depth of water-final in feet.

$d_i$  – depth of water-initial in feet.

D – diameter of casing in feet.

$d_b$  – depth of bottom (initial water column) in feet.  
 $t$  – time interval in hour.

**Table 1 – Percolation Test Results**

Percolation Test Hole No.	Test Hole Depth	Soil Classification	Slowest Percolation Rate, (Gal/Square foot/Day)
SP-1	30.0	SM	3.57
SP-2	30.0	SM	3.45

#### 4.0 DISCUSSION OF RESULTS

##### 4.1 Uniformity of Soil

The soil within the proposed sewage disposal area consists of silty fine to medium grained sand. Most of the soils encountered in the borings were consistent and classified by the USCS classification system as a SM. Given the soils are alluvium, the degree of cementation at specific locations can vary. A slightly faster percolation rate was obtained in percolation test hole SP-2 likely due to the degree cementation of alluvium.

##### 4.2 Sources of Variability or Error

There were no known sources of error. Variability in percolation test rates occurred primarily due to the drilling depth, the slight subsurface material change, and degree of cementation within the alluvial sediments.

##### 4.3 Interpretation of Results

Based on results of percolation testing at the area of the proposed seepage pits, the subject site is believed to be feasible for installation of an on-site sewage disposal system that conforms to the San Bernardino County DEHS requirements. Groundwater was not encountered to up to 40 feet bgs. The proposed OWTS is not anticipated to affect groundwater quality.

#### 5.0 DESIGN

### 5.1 General Criteria

The disposal system for the site should be designed and constructed in accordance with the San Bernardino County DEHS criteria and applicable portion of the California Plumbing Code. The San Bernardino County design criteria can be found in the DEHS publication *Soil Percolation Testing and Reporting Standards for Onsite Wastewater Treatment System Systems*, Revised dated September 2019. In addition, if the seepage pit and tank are proposed to be driven over, they should be designed to a minimum H-20-wheel loading.

### 5.2 Conversion of Percolation Rate to Seepage Pit Design Rates

The existing conventional system was certified by Action Pumping Inc. on July 20, 2023. The existing septic system certification is included in Appendix B. The existing fixture units and total future units will be 28 and 38 fixture units, which are shown on OWTS Fixture Unit Worksheet in Plate No. 1b of **Appendix A**. According to the County project manager Alfonso Fausto, the existing septic system will remain in use, which will be hooked up to 28 fixture units. The extra 10 fixture units will be hooked to the new OWTS. Per California Plumbing Code Table H 201.1(1), a 750-gal septic tank will be required to accommodate the additional wastewater discharge.

Based on percolation test results, the slower percolation rate of 3.45 gal/sf/day obtained from test hole SP-2 is used for the new OWTS design. The seepage pit calculation for a 4-foot diameter seepage pit is shown as follows:

1. The seepage pit design rate:  $1/QX100=28.99$  sf/100 gstc
2. Design depth below inlet=septic tank capacity/  
 $(Q.D.\pi)=750/(3.45*4*3.14)=17.3$  feet

One 4-foot diameter seepage pit having 22 feet in depth and cap depth of 4 feet is recommended for the new OWTS ((22-4) feet perco. depth=18 >17.3 feet required depth). and the same size and depth seepage pit should be

constructed in the future 100% expansion.

### **CLOSURE**


The findings and recommendation of this report were prepared in accordance with generally accepted professional engineering principles and practices in the field of soil mechanics. The conclusions are based on the results of the field exploration and testing combined with an interpolation of soils conditions between the exploratory borings. If conditions are encountered during construction that appear different than those indicated by this report, this firm should be notified.

NOT FOR BID

**APPENDIX A**


**NOT FOR BID**

NOT FOR BID



**1 RENOVATION SITE PLAN**  
SCALE: 1" = 30'-0"

- Legend**
- SP-1 Seepage Pit Test Location
  - Proposed 4-foot diameter seepage pit for present use
  - 4-foot diameter seepage pit for 100% future expansion
  - Existing 5-foot diameter seepage pit
  - Existing 2,500-gal. septic tank
  - 750-gallon Jensen precast septic tank or equivalent





DEMOLITION KEYNOTES	
06 B	REMOVE AND DISPOSE OF EXISTING SHELVES. PATCH & REPAIR IMPACTED WORK AREA.
06 D	REMOVE AND DISPOSE OF EXISTING PORTION OF WALL. PATCH AND REPAIR DAMAGED WALL SURFACES TO MATCH EXISTING AND PREPARE FOR NEW WORK (WHERE OCCURS).
08 A	REMOVE EXISTING DOOR(S), H/M DOOR FRAME, AND THRESHOLD. EXISTING DOOR TO REMAIN. REMOVE DOOR HARDWARE AND REPLACE WITH NEW COMPLIANT TYPE. SEE DOOR SCHEDULE FOR ADDITIONAL INFORMATION.
08 D	REMOVE AND DISPOSE OF PASS THROUGH COUNTER. PREPARE FOR NEW WORK.
09 A	REMOVE AND DISPOSE OF EXISTING CARPET FLOORING. MATERIAL AND ADHESIVE MATERIAL TO ACCOMMODATE NEW FINISH MATERIAL. PREPARE FOR NEW WORK.
09 B	REMOVE AND DISPOSE OF EXISTING VINYL TILE FLOORING. MATERIAL AND ADHESIVE MATERIAL TO ACCOMMODATE NEW FINISH MATERIAL. PREPARE FOR NEW WORK.
09 C	REMOVE AND DISPOSE OF EXISTING RUBBER WALL BASE. PATCH AND REPAIR TO MATCH EXISTING INTERIOR WALLS.
10 A	REMOVE AND SALVAGE EXISTING TOILET PARTITIONS AND ATTACHED TOILET ACCESSORIES.
10 E	REMOVE AND SALVAGE EXISTING GRAB BARS FROM WALL. PATCH REPAIR WALL SURFACE TO MATCH EXISTING.
11 A	REMOVE AND SALVAGE EXISTING REFRIGERATOR. STORE ON SITE, UNLESS OTHERWISE INSTRUCTED.
12 A	REMOVE EXISTING BUILT IN COUNTER OR BUILT IN STORAGE CABINET AND COUNTERTOP.
22 A	REMOVE EXISTING PLUMBING FIXTURE AND ASSOCIATED FITTINGS. CAP UTILITY LINES BELOW WALL/FLOOR SURFACES AS REQUIRED. RECONNECT PIPING TO NEW FIXTURES SHOWN ON RENOVATION PLAN. PATCH AND REPAIR IMPACTED WALL/FLOOR SURFACES.
26 G	REMOVE EXISTING LIGHT SWITCHES AND OUTLETS. SEE ELECTRICAL DRAWINGS FOR ADDITIONAL INFORMATION.

**DEMOLITION NOTES**

- CAP ALL EXISTING UTILITIES & PREPARE FOR NEW WORK AS REQUIRED.
- PROVIDE ALL LABOR, MATERIAL, AND EQUIPMENT NECESSARY TO COMPLETE DEMOLITION WORK AS INDICATED ON DRAWINGS AND SPECIFICATIONS AND AS REQUIRED TO ACCOMMODATE NEW CONSTRUCTION.
- PATCH, REPAIR, AND RESTORE ALL AREAS DAMAGED BY THE CONSTRUCTION WORK AND RESTORATION TO MATCH CONDITION OF ADJACENT UNDISTURBED SURFACES.
- REMOVE FROM THE SITE ALL MATERIAL RESULTING FROM THE DEMOLITION WORK IN SUCH A MANNER AS TO AVOID CREATING A NUISANCE. DISPOSE OF ALL MATERIALS FROM THE SITE ON A DAILY BASIS AT AN ADDITIONAL COST TO THE OWNER.
- DISPOSE OF ALL MATERIAL RESULTING FROM THE DEMOLITION WORK IN ACCORDANCE WITH ALL APPLICABLE LAWS AND REGULATIONS, INCLUDING THOSE GOVERNING NOISE, DUST, AND DIRT CONTROL, DISPOSAL OF HAZARDOUS MATERIALS, AND REQUIREMENTS OF THE LOCAL AIR QUALITY MANAGEMENT DISTRICT.


**WALL TYPE**



**1 DEMOLITION FLOOR PLAN**  
SCALE: 1/4" = 1'-0"


<b>UNDERGROUND SERVICE ALERT</b> <p>CALL TOLL FREE 1-800-227-2600 OR 811</p> <p>TWO WORKING DAYS BEFORE YOU DIG</p>	<b>BENCHMARK</b> 	<b>BASE OF BEARING:</b> 		<b>BOA Architecture</b> Government Services 1511 Coia Ave. Long Beach, CA 90813 Tel: 562-912-7900 PREPARED UNDER THE SUPERVISION OF: EDWARD LOK NG C-16840 ARCHITECT NO. DATE 2-8-2024	<b>REVISIONS</b> <table border="1"> <thead> <tr> <th>No.</th> <th>Date</th> <th>By</th> <th>Rev</th> <th>Ck</th> <th>Date</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>	No.	Date	By	Rev	Ck	Date							<b>PLANS APPROVED BY:</b> SAN BERNARDINO COUNTY - PUBLIC WORKS SPECIAL DISTRICTS ASSISTANT DIRECTOR PROJECT MANAGER OPS. DIVISION MANAGER P.M. DIVISION MANAGER 2-8-2024 DATE	<b>IMPROVEMENT PLANS</b> WONDER VALLEY COMMUNITY CENTER SITE IMPROVEMENTS DEMOLITION FLOOR PLAN DWG. NO. FILE NO. SHEET 4 OF
No.	Date	By	Rev	Ck	Date														

- NOTES:**
- MAINTAIN 4" W SERVICE FROM (C) W SERVICE ON SITE TO POINTS OF CONNECTION
  - PROVIDE WATER CLOSET WC-1 (REPLACEMENT-IN-KIND)
  - PROVIDE LAVATORY L-1 (REPLACEMENT-IN-KIND)
  - PROVIDE URINAL UB-1 (REPLACEMENT-IN-KIND)
  - PROVIDE MOP SINK MS-1 (REPLACEMENT-IN-KIND)
  - PROVIDE 3-COMPARTMENT SINK 3CS-1 (REPLACEMENT-IN-KIND)
  - PROVIDE DRINKING FOUNTAIN DF-1 (REPLACEMENT-IN-KIND)
  - PROVIDE 1-COMPARTMENT SINK 1CS-1
  - PROVIDE HAND SINK HS-1
  - PROVIDE FLOOR SINK
  - PROVIDE PREP GREASE INTERCEPTOR G-1
  - PROVIDE SHAMPLING BOX SB-1
  - PROVIDE CONCRETE APRON
  - PROVIDE 2" V SERVICE FROM DISCHARGE OF G TO TERMINATION ABOVE ROOF. COORDINATE ROUTING, TERMINATION, CONCEALMENT WITH GENERAL CONTRACTOR
  - DEMO WASTE, VENT SERVICES FROM POC TO POC / TO FIXTURES. DEMO ASSOCIATED VENT SERVICES TO POC AT UNDERSIDE OF ROOF. MAINTAIN WORK WITHIN CONVEYS OF KITCHEN AS POSSIBLE TO MINIMIZE SLAB WORK
  - MAINTAIN 60" W SERVICES UNLESS OTHERWISE NOTED
  - COORDINATE REPAIR OF HARDSCAPE, LANDSCAPE WITH GENERAL CONTRACTOR
  - PROVIDE (N) W SERVICE FROM POC TO (N) SEWAGE PIT



**RENO ENLARGE FLOOR PLAN - WASTE & VENT**  
SCALE: 1/4" = 1'-0"

- NOTES:**
- MAINTAIN 1" CW SERVICE FROM (C) CW SERVICE ON SITE TO POINTS OF CONNECTION
  - PROVIDE WATER CLOSET WC-1 (REPLACEMENT-IN-KIND)
  - PROVIDE LAVATORY L-1 (REPLACEMENT-IN-KIND)
  - PROVIDE URINAL UB-1 (REPLACEMENT-IN-KIND)
  - PROVIDE MOP SINK MS-1 (REPLACEMENT-IN-KIND)
  - PROVIDE 3-COMPARTMENT SINK 3CS-1 (REPLACEMENT-IN-KIND)
  - PROVIDE DRINKING FOUNTAIN DF-1 (REPLACEMENT-IN-KIND)
  - PROVIDE 1-COMPARTMENT SINK 1CS-1
  - PROVIDE HAND SINK HS-1
  - NOT USED
  - PROVIDE WATER HEATER WH-1 (REPLACEMENT-IN-KIND)
  - MAINTAIN CW SERVICE IN SPACE TO POC
  - PROVIDE CW SERVICE FROM POC IN VICINITY OF POINTS OF USE
  - REPAIR SLAB FOR BAY CUTS. RESTORATION OF FLOOR TO ORIGINAL CONDITION BY GENERAL CONTRACTOR
  - RESTORATION OF WALL TO ORIGINAL CONDITION BY GENERAL CONTRACTOR
  - RESTORATION OF HAND LIE CEILING TO ORIGINAL CONDITION BY GENERAL CONTRACTOR



**RENO ENLARGE FLOOR PLAN - HOT & COLD WATER**  
SCALE: 1/4" = 1'-0"

<b>UNDERGROUND SERVICE ALERT</b> <p>CALL TOLL FREE 1-800-227-2600 OR 811</p> <p>TWO WORKING DAYS BEFORE YOU DIG</p>	<p>SAN BERNARDINO COUNTY DEPARTMENT OF PUBLIC WORKS SPECIAL DISTRICTS 225 WEST HOSPITALITY LANE, 2ND FLOOR SAN BERNARDINO, CA 92411-2650 (SITE CONTACT - FRANK HAGGARD) 760-366-8415 (EMAIL - FHAGGARD@SDD.SBCOUNTY.GOV)</p>		<b>ENGINEERING CENTER (SPECIAL DISTRICTS)</b> 1885 FALSBURY AVENUE, SUITE 300 FONTANA, CALIF. 92430 951-845-8333 951-845-4338 (F) SDD@SBCOUNTY.GOV PREPARED UNDER THE SUPERVISION OF: PROFESSIONAL ENGINEER NAME DATE	<b>APPROVALS</b> <table border="1"> <thead> <tr> <th>DATE</th> <th>BY</th> <th>FOR</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>	DATE	BY	FOR				<b>PLANS PROVIDED BY:</b> SAN BERNARDINO COUNTY - PUBLIC WORKS SPECIAL DISTRICTS ASSISTANT DIRECTOR PROJECT MANAGER OPS. DIVISION MANAGER P.M. DIVISION MANAGER	<b>WONDER VALLEY RE-MODEL</b> 80526 1/2 AMBOY ROAD WONDER VALLEY, CA 92277 Alfonso.Fausto@SDD.SBCounty.gov Phone: 909-386-8827 Cell: (909)771-1702	DWG. NO. 30.30.0149 SHEET NO. P-2.1 SHEET 4 OF 7
DATE	BY	FOR											



**Existing Floor Plan and Renovation Floor Plan**  
 80256 Amboy Road, Twentynine Palms, CA 92277

By: MC Date: 03/2024

Project No.: 0904-13.1 Plate No. 1a

# ONSITE WASTEWATER TREATMENT SYSTEM FIXTURE UNIT WORKSHEET

This worksheet shall be used to determine the existing fixture unit count and the proposed fixture unit count for all planned alterations to existing structures. Floor plans may be required to confirm both existing and proposed conditions. When only proposing a new OWTS system, complete the proposed column (B) of the worksheet. The completed worksheet shall be certified by a Registered Civil Engineer (R.C.E.), R.E.H.S, Registered Geologist (R.G.), or an "A", "C-42", "C-36" Contractors License.

Date:	File Index Number:
Applicant: Wonder Valley Community Center	Address: 80526 Amboy Road
Worksheet Certified By (print name):	Worksheet Certified By (signature):
Applicable California State License or Registration Type:	State License or Registration Number and Expiration Date:
Number of Fixtures (existing):	Number of Fixtures (future):

Type of Plumbing Fixture	Existing Fixtures	+	Proposed Fixtures	+	Total Fixtures	x	Fixture Unit Value	=	Existing Fixture Unit	Future Fixture Unit
	"A"	+	"B"	+	"(A+B)"	x	"C"	=	"(A x C)"	"(A+B) x C"
Drinking Fountain		+		+		x	0.5	=		
Floor Drain		+		+		x	2	=		
Floor Drain (Emergency - i.e. in restrooms)		+		+		x	0	=		
Floor Sink (1.5" Trap)		+		+		x	3	=		
Floor Sink (2" Trap)		+		+		x	4	=		
Floor Sink (3" Trap)		+		+		x	6	=		
Floor Sink (4" Trap)		+		+		x	8	=		
3 Compartment Sink (Does not count floor sink)		+	4	+	4	x	3	=		12
Hand Sink	3	+	-2	+	1	x	1	=	3	1
Mop Sink	1	+	0	+	1	x	3	=	3	3
Bar Sink		+		+		x	2	=		
Urinal	1	+	0	+	1	x	2	=	2	2
Water Closet (Flush Toilet)	3	+	0	+	3	x	6	=	18	18
Lavatory	2	+	0	+	2	x	1	=	2	2
Food Prep Sink		+		+		x	3	=		
Other (CPC Table 702.1)		+		+		x		=		

For more information review the current California Plumbing Code.

**TOTAL EXISTING FIXTURE UNITS**

28

**TOTAL FUTURE FIXTURE UNITS**

38

## KEY TO LOGS

SOILS CLASSIFICATION							
MAJOR DIVISIONS			GRAPHIC LOG	USCS SYMBOL	TYPICAL NAMES		
<b>COARSE GRAINED SOILS</b>	<b>GRAVELS</b>	<b>CLEAN GRAVELS</b>		<b>GW</b>	WELL-GRADED GRAVELS, GRAVEL-SAND MIXTURES, LITTLE OR NO FINES		
		LESS THAN 5% FINES		<b>GP</b>	POORLY-GRADED GRAVELS, GRAVEL-SAND MIXTURES, LITTLE OR NO FINES		
		<b>GRAVELS WITH FINES</b>		<b>GM</b>	SILTY GRAVELS, GRAVEL-SAND-SILT MIXTURES		
	MORE THAN 50% OF COARSE FRACTION IS LARGER THAN NO. 4 SIEVE	<b>GRAVELS WITH FINES</b>	MORE THAN 12% FINES		<b>GC</b>	CLAYEY GRAVELS, GRAVEL-SAND-CLAY MIXTURES	
			<b>CLEAN SANDS</b>		<b>SW</b>	WELL-GRADED SANDS, GRAVELLY SANDS, LITTLE OR NO FINES	
		<b>SANDS</b>	LESS THAN 5% FINES		<b>SP</b>	POORLY-GRADED SANDS, GRAVELLY SANDS, LITTLE OR NO FINES	
			<b>SANDS WITH FINES</b>		<b>SM</b>	SILTY SANDS, SAND-SILT MIXTURES	
			MORE THAN 12% FINES		<b>SC</b>	CLAYEY SANDS, SAND-CLAY MIXTURES	
			<b>SILTS AND CLAYS</b>	LIQUID LIMIT IS LESS THAN 50		<b>ML</b>	INORGANIC SILTS AND VERY FINE SANDS, ROCK FLOUR, SILTY OR CLAYEY FINE SANDS OR CLAYEY SILTS WITH SLIGHT PLASTICITY
				<b>SILTS AND CLAYS</b>	LIQUID LIMIT IS 50 OR MORE		<b>CL</b>
LIQUID LIMIT IS 50 OR MORE		<b>OL</b>			ORGANIC SILTS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY		
50% OR MORE OF MATERIAL IS SMALLER THAN NO. 200 SIEVE SIZE	<b>SILTS AND CLAYS</b>	LIQUID LIMIT IS 50 OR MORE		<b>MH</b>	INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS FINE SANDY OR GRAVELLY ELASTIC SILTS		
		LIQUID LIMIT IS 50 OR MORE		<b>CH</b>	INORGANIC CLAYS OF HIGH PLASTICITY, FAT CLAYS		
		LIQUID LIMIT IS 50 OR MORE		<b>OH</b>	ORGANIC CLAYS OF MEDIUM TO HIGH PLASTICITY, ORGANIC SILTS		
<b>HIGHLY ORGANIC SOILS</b>				<b>PT</b>	PEAT AND OTHER HIGHLY ORGANIC SOILS		

GRAIN SIZES							
SILT AND CLAY	SAND			GRAVEL		COBBLES	BOULDERS
	FINE	MEDIUM	COARSE	FINE	COARSE		
	#200	#40	#10	#4	3/4"	3"	12"
SIEVE SIZES							



# Hilltop Geotechnical

786 S. Gifford Avenue, San Bernardino, California, 92408

Phone: 909 890 9079

**Boring No.: SP-1**

**HILLTOP GEOTECHNICAL**  
INCORPORATED

Latitude :	Drill Supplier : Choice Drilling	Job Number : 0904-13	Sheet : 1 OF 1
Longitude :	Driller Company : Choice Drilling	Client : County of San Bernardino Dept of Public Works - Pavement Management	
Elevation : Not Surveyed	Logged By : Nathan Lankey	Project : CSA Wonder Valley Comm. Center Perc	
Total Depth : 40 ft	Date : 02/16/2024	Location : 80526 Amboy Road, Twentynine Palms, CA, USA	

Depth (ft)	Samples		Blows per 6" (SPT)	Blows per 6" (ModCal)	Graphic Log	Soil Origin	Classification Code	Material Description	Testing			
	Bulk								% Fines	Moisture %	Dry Density (pcf)	Other
1	X				[Graphic Log]	Alluvium	SM	SILTY SAND (SM) : silty fine to medium grained sand, loose to medium dense, moist, trace to few fine to medium sized, gravel, light yellowish brown.				
2												
3												
4												
5												
6												
7												
8												
9												
10												
11												
12												
13												
14												
15												
16												
17												
18												
19												
20												
21												
22												
23												
24												
25												
26												
27												
28												
29												
30												
31												
32												
33												
34												
35												
36												
37												
38												
39												
40												
41								B-1 Terminated at 40ft (No caving observed. No ground encountered.)				

NOT FOR BID



# Hilltop Geotechnical

786 S. Gifford Avenue, San Bernardino, California, 92408

Phone: 909 890 9079

**Boring No.: SP-2**

**HILLTOP GEOTECHNICAL**  
INCORPORATED

Latitude :	Drill Supplier : Choice Drilling	Job Number : 0904-13	Sheet : 1 OF 1
Longitude :	Driller Company : Choice Drilling	Client : County of San Bernardino Dept of Public Works - Pavement Management	
Elevation : Not Surveyed	Logged By : Nathan Lankey	Project : CSA Wonder Valley Comm. Center Perc	
Total Depth : 30 ft	Date : 02/16/2024	Location : 80526 Amboy Road, Twentynine Palms, CA, USA	

Depth (ft)	Samples	Blows per 6" (SPT)	Blows per 6" (ModCal)	Graphic Log	Soil Origin	Classification Code	Material Description	Testing			
								% Fines	Moisture %	Dry Density (pcf)	Other
1				[Graphic Log Area]	Alluvium	SM	SILTY SAND (SM) : silty fine to medium grained sand, loose to medium dense, moist, trace to few fine to medium sized gravel, light yellowish brown.				
2											
3											
4											
5											
6											
7											
8											
9											
10											
11											
12											
13											
14											
15											
16											
17											
18											
19											
20											
21											
22											
23											
24											
25											
26											
27											
28											
29											
30											
31											



## SEEPAGE PIT PERCOLATION DATA SHEET

Project Name: Wonder Valley Community Center  
 Test Hole Number: SP-1  
 Depth of Boring in feet: 30.0  
 Diameter of Boring in feet: 0.67

Project Number: 0904-13  
 Date Tested: 2/20/2024  
 Tested By: NL  
 Hours Presatura 1

Depth of Bottom (ft)	Time Initial	Time Final	Time Interval (minutes)	Depth of Water - Initial (ft)	Depth of Water - Final (ft)	Change in Water Level (ft)	L <sub>average</sub> (ft)	Rate, Q (gal/ft <sup>2</sup> /day)
30.0	8:50:00	9:20:00	30	0.00	14.00	14.00	23.00	7.34
29.4	9:30:00	10:00:00	30	0.00	12.00	12.00	24.00	6.03
28.9	10:03:00	10:33:00	30	0.00	9.40	9.40	25.30	4.48
28.5	10:35:00	11:05:00	30	0.00	8.80	8.80	25.60	4.15
28.3	11:08:00	11:38:00	30	0.00	8.50	8.50	25.75	3.98
28.0	11:40:00	12:10:00	30	0.00	8.50	8.50	25.75	3.98
27.8	12:13:00	12:43:00	30	0.00	8.00	8.00	26.00	3.71
27.5	12:46:00	13:16:00	30	0.00	8.20	8.20	25.90	3.82
27.0	13:20:00	13:50:00	30	0.00	8.00	8.00	26.00	3.71
27.0	13:52:00	14:22:00	30	0.00	8.00	8.00	26.00	3.71
26.8	14:25:00	14:55:00	30	4.00	10.80	6.80	22.60	3.63
26.7	14:48:00	15:18:00	30	4.00	10.70	6.70	22.65	3.57

Average Rate (gal/ft<sup>2</sup>/day): 4.34



## SEEPAGE PIT PERCOLATION DATA SHEET

Project Name: Wonder Valley Community Center  
 Test Hole Number: SP-2  
 Depth of Boring in feet: 30.0  
 Diameter of Boring in feet: 0.67

Project Number: 0904-13  
 Date Tested: 2/20/2024  
 Tested By: NL  
 Hours Presatura 1

Depth of Bottom (ft)	Time Initial	Time Final	Time Interval (minutes)	Depth of Water - Initial (ft)	Depth of Water - Final (ft)	Change in Water Level (ft)	L <sub>average</sub> (ft)	Rate, Q (gal/ft <sup>2</sup> /day)
30.0	8:54:00	9:24:00	30	0.00	13.50	13.50	23.25	7.00
29.6	9:35:00	10:05:00	30	0.00	12.00	12.00	24.00	6.03
29.0	10:08:00	10:38:00	30	0.00	9.70	9.70	25.15	4.65
28.7	10:40:00	11:10:00	30	0.00	8.50	8.50	25.75	3.98
28.5	11:13:00	11:43:00	30	0.00	8.50	8.50	25.75	3.98
28.2	11:45:00	12:15:00	30	0.00	8.30	8.30	25.85	3.87
28.0	12:17:00	12:47:00	30	0.00	8.20	8.20	25.90	3.82
27.8	12:48:00	13:18:00	30	0.00	8.00	8.00	26.00	3.71
27.5	13:22:00	13:52:00	30	0.00	7.80	7.80	26.10	3.60
27.4	13:54:00	14:24:00	30	0.00	7.70	7.70	26.15	3.55
27.2	14:25:00	14:55:00	30	4.00	10.60	6.60	22.70	3.51
27.2	14:47:00	15:17:00	30	4.00	10.50	6.50	22.75	3.45

Average Rate (gal/ft<sup>2</sup>/day): 4.26

## **APPENDIX B**

### **COMMERCIAL ONSITE WASTEWATER TREATMENT SYSTEM (OWTS) CERTIFICATION**

**NOT FOR BID**



## COMMERCIAL ONSITE WASTEWATER TREATMENT SYSTEM (OWTS) CERTIFICATION

Certification shall be completed by a state licensed contractor (A, C-36, or C-42) or other qualified professional/service provider such as: Registered Professional Engineer (R.P.E.), Certified Engineering Geologist (C.E.G.), Registered Environmental Health Specialist (R.E.H.S.), etc. For more information, call 800-442-2283.

APPLICANT INFORMATION	
Property Owner: Wonder Valley Community Center	Applicant Name: <u>ALFONSO FAUSTO</u>
Property Address: 80526 Amboy Road	Phone Number: (760) 366-8415
Mailing Address:	Email: <u>alfonso.fausto@sdd.sbcounty.gov</u>
Type of Facility (restaurant, apartment, warehouse, etc.): <u>Community Center</u>	
APN: <u>06265104</u>	Project Number: <u>30.30.0149</u>

OWTS INFORMATION	
<b>COMMERCIAL DEVELOPMENT</b>	Types of Fixtures (per CPC; indicate type and number of each) <b>Complete the "Onsite Wastewater Treatment System Fixture Unit Worksheet" (Page 4).</b>
	Total Number of Fixture Units: <u>28</u> Influent Strength: <input checked="" type="checkbox"/> Normal <input type="checkbox"/> High Strength <input type="checkbox"/> Weak

<b>TANKS</b>	Type of OWTS: <input checked="" type="checkbox"/> Conventional <input type="checkbox"/> Advanced*	Dimensions (LxWxD): <u>16 X 4.2 X 4</u> ft.
	Effluent Filter: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Tank Capacity: 2500 gallons
	Type of Cover (specify): concrete	
	Depth of Cover:                      ft.                      26 in.	Number of Compartments: 2
	Tank Function: <input checked="" type="checkbox"/> Septic <input type="checkbox"/> Treatment <input type="checkbox"/> Pump Vault <input type="checkbox"/> Dosing <input type="checkbox"/> Grease	
	Inspection Risers: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	Risers Diameter:
	Liquid Level in Tank: <input checked="" type="checkbox"/> Normal at inlet level <input type="checkbox"/> Below inlet level <input type="checkbox"/> Above inlet level	Septage Levels: Scum: <u>6</u> in Effluent:                      in Sludge: <u>12</u> in
* Complete page 5 if using an advanced OWTS system.		

<b>PUMP STATION</b>	Does the system have a pumping station? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No    Complete the section below if "Yes".	
	Pump Vault Type: <input type="checkbox"/> In Tank Vault <input type="checkbox"/> Pump Station Vault <input type="checkbox"/> Dosing	Access: <input type="checkbox"/> Yes <input type="checkbox"/> No
	Pump Vault Material: <input type="checkbox"/> Concrete <input type="checkbox"/> Plastic <input type="checkbox"/> Other:	
	Diameter:	Floats: <input type="checkbox"/> Pass <input type="checkbox"/> Needs Adjustment <input type="checkbox"/> Fail
	Condition of Vault: <input type="checkbox"/> Acceptable <input type="checkbox"/> Structurally Unsound <input type="checkbox"/> Infiltration <input type="checkbox"/> Exfiltration	
	Pumps: <input type="checkbox"/> Simplex <input type="checkbox"/> Duplex <input type="checkbox"/> Other:	Pumps Elevated: <input type="checkbox"/> Yes <input type="checkbox"/> No
	Pumps Operation: <input type="checkbox"/> Pass <input type="checkbox"/> Fail <input type="checkbox"/> Pump Replaced	Alarms: <input type="checkbox"/> Yes <input type="checkbox"/> No
	High Water Alarm: <input type="checkbox"/> Yes <input type="checkbox"/> No	Alarm Notification: <input type="checkbox"/> Telemetry <input type="checkbox"/> Visual <input type="checkbox"/> Audible

**OWTS INFORMATION, CONTINUED**

<b>DISPERSAL SYSTEM</b>	Type of Disposal Area: <input checked="" type="checkbox"/> Seepage Pit <input type="checkbox"/> Leachlines <input type="checkbox"/> Other:		
	Distance from Well: <u>150</u> ft.	Distance from Foundation: <u>10</u> ft.	
	Distance from Nearest Lot Line: Front: <u>35</u> ft.    Side:    ft.    Rear:    ft.		
	Specify any Damage or Defects Observed:		

<b>SEEPAGE PITS</b>	Number of Pits: <u>1</u>	Outside Diameter: <u>5</u> ft.	Depth: <u>24</u> ft.
	Depth of Pit Below Inlet: <u>32</u> ft.	Lining Material (specify): <u>CRACK ROCK</u>	
	Depth of Liquid: <u>10</u> ft.	Access Riser: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	

<b>LEACHLINES</b>	Number of Lines:	Trench Width:	Average Length of Lines:
	Total Absorption Area (bottom of trenches):    sq. ft.		Depth (finish grade to top of line):    in.
	Distance Between Lines:    ft.	Type of Filter Material Beneath Line:	
	Depth of Material Above Line:    in.	Depth of Material Beneath Line:    in.	
	<input type="checkbox"/> Plastic Leaching Chambers <input type="checkbox"/> Bundled Expanded Polystyrene Synthetic Aggregate Units		
	Specify Indications of Previous System Failures i.e., odors, seepage, etc. <i>(use additional paper if necessary)</i> :		

<b>DISTRIBUTION</b>	Distribution Type: <input type="checkbox"/> Direct Connection <input type="checkbox"/> Box <input type="checkbox"/> Manifold <input type="checkbox"/> Other:		
	Material: <input type="checkbox"/> Concrete <input type="checkbox"/> Plastic <input type="checkbox"/> Other:		
	Condition: <input type="checkbox"/> Pass <input type="checkbox"/> Damaged <input type="checkbox"/> Failed	Access Riser to Grade: <input type="checkbox"/> Yes <input type="checkbox"/> No	
	Observed Deficiencies: <input type="checkbox"/> Cracks <input type="checkbox"/> Evidence of Ponding <input type="checkbox"/> Roots <input type="checkbox"/> Sludge <input type="checkbox"/> Unlevel <input type="checkbox"/> Water Infiltration		

<b>HYDRAULIC TEST</b>	Dye Test: <input type="checkbox"/> Yes <input type="checkbox"/> No	Number of Gallons (500 gallon minimum):
	Length of Time Added (60 minute minimum):	Liquid Level Rise:    in.
	Time to Return to Initial (30 minute minimum):	
	Comments (length of vacancy, irregularities, etc.):	

**NOTE: PLEASE ATTACH TEST RESULTS AND COPIES OF ANY BUILDING PERMITS.**

# ONSITE WASTEWATER TREATMENT SYSTEM FIXTURE UNIT WORKSHEET

This worksheet shall be used to determine the existing fixture unit count and the proposed fixture unit count for all planned alterations to existing structures. Floor plans may be required to confirm both existing and proposed conditions. When only proposing a new OWTS system, complete the proposed column (B) of the worksheet. The completed worksheet shall be certified by a Registered Civil Engineer (R.C.E.), R.E.H.S, Registered Geologist (R.G.), or an "A", "C-42", "C-36" Contractors License.

Date:08/28/2023	File Index Number:
Applicant:Wonder Valley Community Center	Address:80526 Amboy Road
Worksheet Certified By (print name): Action Pumping Inc	Worksheet Certified By (signature):
Applicable California State License or Registration Type: C42. C36	State License or Registration Number and Expiration Date: 436154
Number of Fixtures (existing):	Number of Fixtures (future):

Type of Plumbing Fixture	Existing Fixtures	+	Proposed Fixtures	+	Total Fixtures	x	Fixture Unit Value	=	Existing Fixture Unit	Future Fixture Unit
	"A"	+	"B"	+	"(A+B)"	x	"C"	=	"(A x C)"	"(A+B) x C"
Drinking Fountain		+		+		x	0.5	=		
Floor Drain		+		+		x	2	=		
Floor Drain (Emergency - i.e. in restrooms)		+		+		x	0	=		
Floor Sink (1.5" Trap)		+		+		x	3	=		
Floor Sink (2" Trap)		+		+		x	4	=		
Floor Sink (3" Trap)		+		+		x	6	=		
Floor Sink (4" Trap)		+		+		x	8	=		
3 Compartment Sink (Does not count floor sink)		+		+		x	3	=		
Hand Sink	3	+	0	+	3	x	1	=	3	
Mop Sink	1	+	0	+	1	x	3	=	3	
Bar Sink		+		+		x	2	=		
Urinal	1	+	0	+	1	x	2	=	2	
Water Closet (Flush Toilet)	3	+	0	+	3	x	6	=	18	
Lavatory	2	+	0	+	2	x	1	=	2	
Food Prep Sink		+		+		x	3	=		
Other (CPC Table 702.1)		+		+		x		=		

For more information review the current California Plumbing Code.

**TOTAL EXISTING FIXTURE UNITS**

28

**TOTAL FUTURE FIXTURE UNITS**

0

## ALTERNATIVE TREATMENT SYSTEM INFORMATION FORM


This page is only required for OWTS with Alternative or Advanced Treatment Systems. Attach a copy of the last maintenance report provided by the service provider.

**NOTE: ADVANCED OWTS WILL REQUIRE APPROVAL FROM SERVICE PROVIDER**

Advanced Treatment Manufacturer:	Model:
EHS Permit Number:	
Advanced System Information: <input type="checkbox"/> Secondary Treatment <input type="checkbox"/> Disinfection <input type="checkbox"/> De-Nitrification	
Dimensions (LxWxD):    x    x    ft.	Tank Capacity (gallons):
Wastewater Tank (other than a septic tank): <input type="checkbox"/> Yes <input type="checkbox"/> No	
Type of Tank: <input type="checkbox"/> Treatment <input type="checkbox"/> Holding <input type="checkbox"/> Equalization <input type="checkbox"/> Dosing/Pumping	
System Functioning in Accordance to Design: <input type="checkbox"/> Yes <input type="checkbox"/> No	
System Controls: <input type="checkbox"/> Yes <input type="checkbox"/> No	Controls Tested: <input type="checkbox"/> Yes <input type="checkbox"/> No
Pumping Systems: <input type="checkbox"/> Yes <input type="checkbox"/> No	Pumping System Functional: <input type="checkbox"/> Yes <input type="checkbox"/> No
Blower Operational: <input type="checkbox"/> Yes <input type="checkbox"/> No	Maintenance Required: <input type="checkbox"/> Yes <input type="checkbox"/> No
Disinfection Unit: <input type="checkbox"/> Yes <input type="checkbox"/> No	Disinfection Unit Operational: <input type="checkbox"/> Yes <input type="checkbox"/> No
Disinfection Unit Type: <input type="checkbox"/> UV <input type="checkbox"/> Chlorination/Dechlorination <input type="checkbox"/> Ozone	
Fixed Film Aerobic System Media Condition: <input type="checkbox"/> Good <input type="checkbox"/> Poor <input type="checkbox"/> Replaced <input type="checkbox"/> N/A	
Media Filter System Condition of Media: <input type="checkbox"/> Good <input type="checkbox"/> Poor <input type="checkbox"/> Replaced <input type="checkbox"/> N/A	
Spray System Condition: <input type="checkbox"/> Good <input type="checkbox"/> Poor <input type="checkbox"/> Repaired	Pressure Dosed: <input type="checkbox"/> Yes <input type="checkbox"/> No
Service Provider:	Contract Expiration Date:
Date of Last Maintenance:	Status of Last Maintenance:
Specify any Damage or Defects Observed:	
<p><b>Indemnification</b> – The Contractor agrees to indemnify, defend (with counsel reasonably approved by County) and hold harmless the County and its authorized officers, employees, agents and volunteers from any and all claims, actions, losses, damages, and/or liability arising out of this contract from any cause whatsoever, including the acts, errors or omissions of any person and for any costs or expenses incurred by the County on account of any claim except where such indemnification is prohibited by law. This indemnification provision shall apply regardless of the existence or degree of fault of indemnitees. The Contractor’s indemnification obligation applies to the County’s “active” as well as “passive” negligence but does not apply to the County’s “sole negligence” or “willful misconduct” within the meaning of Civil Code Section 2782.</p>	
I certify that, to the best of my knowledge and ability, the information above is correct.	
<input checked="" type="checkbox"/> <b>Electronic Signature Only:</b> By checking this box, I confirm I am submitting this application electronically and that the information on this form is true and correct. I also acknowledge that I have read, understand and accept any terms and conditions of this form.	
Signature:	
Print Name:	Inspection Date:

# ONSITE WASTEWATER TREATMENT SYSTEM AREA INFORMATION (REQUIRED)

In the space provided, show the location of the tank and disposal area in relation to the buildings and other landmarks (i.e. wells, trees, shrubs, driveways, parking, paving, drainage courses, property lines, etc.). Indicate if only a cesspool is present.



It is the opinion of the certifier that this sewage disposal system:

Meets current code.  
 Can be expected to function satisfactorily and is not likely to create any unsanitary conditions.

OR

Cannot be expected to function satisfactorily.

**Electronic Signature Only:** By checking this box, I confirm I am submitting this application electronically and that the information on this form is true and correct. I also acknowledge that I have read, understand and accept any terms and conditions of this form.

Signature: <i>Jason Mahaffey</i>	Date: 07/20/23	Phone Number: 7603650861
Type of License: C42, C36	Reg. Number:	Expiration: 03/2024
Name and Address of Certifier: Jason Mahaffey, 7361 Wamego Trail , Yucca Valley Ca 92284		
<b>For Office Use Only</b>		
PE:	Record ID:	FA Number:
Reviewed By:	Date:	Fee:
Comments:		Late Fee: <input type="checkbox"/> Y <input type="checkbox"/> N