Company Name:San Bernadino CountyDate:September 19, 2023Building Name:303 W. 5th StreetJob Number:23005335.00

Street Address: 303 W. 5th Street Engineer: Craig Chamberlain, S.E.

San Bernadino, CA, USA 92401 PE Number/State: CA SE 4588

MODIFIED FEMA-310 WORKSHEET

RM1(5AA)Reinforced Masonry Bearing Walls w/ Flexible Diaphragms

Category	Range	Typical	Modifier	
GENERAL BUILDING FEATURES				
Complete load path No adjacent buildings Interior mezzanines adequately braced No strength irregularity No soft story No geometrical irregularities No mass irregularity No vertical discontinuities Deflection compatibility	T, F T, F N/A, T, F T, F T, F T, F T, F T, F	T T T T T T T	T T T T T T T T T T T T T T T T	
LATERAL FORCE RESISTING SYSTEM				
Redundancy Shear stress check of shear walls Reinforcing steel Adequate reinforcing at openings Stable wall proportions	T, F, 0-10 T, F, 0-15 T, F, 0-5 N/A, T, F, 0-5 T, F, 0-5	0 5 2 2 2	1 T 2 2 2 2	
CONNECTIONS				
Adequate wall anchorage Walls doweled into foundation Adequate girder to column/wall connection Wood ledgers not in cross grain bending Adequate wall anchor spacing Adequate stiffness of wall anchors	T, F, 0-10 T, F, 0-10 T, F, 0-15 N/A, T, F, 0-10 T, F, 0-10 T, F, 0-10	0 0 0 0 0	0 0 0 N/A 0 0	
FLOOR DIAPHRAGMS				
Cross Ties Limited diaphragm openings at shear walls Limited openings at exterior shear walls Reinforcing at re-entrant corners Adequate reinforcing at openings Adequate straight sheathing aspect ratios Large spans adequately sheathed Unblocked diaphragms meet requirements Untopped diaphragms meet requirements Other diaphragms meet requirements	T, F, 0-10 N/A, T, F, 0-5 N/A, T, F, 0-5 N/A, T, F, 0-10 N/A, T, F, 0-5 N/A, T, F, 0-5 N/A, T, F, 0-5 N/A, T, F, 0-5 N/A, T, F, 0-5	5 2 2 0 0 2 2 2 2 2 2	2 N/A N/A N/A N/A N/A N/A N/A N/A N/A	
Collectors	T, F, 0-5	2	2	



Company Name:San Bernadino CountyDate:September 19, 2023Building Name:303 W. 5th StreetJob Number:23005335.00

Street Address: 303 W. 5th Street Engineer: Craig Chamberlain, S.E.

San Bernadino, CA, USA 92401 PE Number/State: CA SE 4588

MODIFIED FEMA-310 WORKSHEET

Category	Range	Typical	Modifier					
ROOF DIAPHRAGM (ONLY IF 5 STORIES OR LESS)								
Cross Ties Limited diaphragm openings at shear walls Limited openings at exterior shear walls Reinforcing at re-entrant corners Adequate reinforcing at openings Adequate straight sheathing aspect ratios Large spans adequately sheathed Unblocked diaphragms meet requirements Untopped diaphragms meet requirements Other diaphragms meet requirements Collectors	T, F, 0-10 N/A, T, F, 0-5 N/A, T, F, 0-5 N/A, T, F, 0-10 N/A, T, F, 0-5 N/A, T, F, 0-5 N/A, T, F, 0-5 N/A, T, F, 0-5 N/A, T, F, 0-5 T, F, 0-5	5 2 2 0 0 2 2 2 2 2 2	5 2 0 0 N/A N/A N/A 2 2 2					
UNUSUAL CONDITIONS								
Little deterioration of masonry units Little deterioration of masonry joints Insignificant reinforced masonry wall cracks Little deterioration of wood Little foundation damage Little foundation deterioration Adequate overturning resistance Ties between foundation elements Lateral force on deep foundations Pole buildings Insignificant sloping at site SITE DEPENDENT HAZARDS - ACTIVE FAULT	T, F, 0-5 T, F, 0-5 T, F, 0-5 N/A, T, F, 0-5 T, F, 0-5 T, F, 0-5 T, F, 0-5 N/A, T, F, 0-5 N/A, T, F, 0-5 N/A, T, F, 0-5	2 2 2 2 2 2 2 2 2 2 0 0	2 2 N/A 2 2 2 2 2 N/A N/A N/A 0					
Surface fault rupture	N/A, 0-50	0	0					
NONSTRUCTURAL EXTERIOR 'WALLS'								
Cladding, glazing, veneer Chimneys	N/A, T, F, 0-10 N/A, T, F, 0-5	5 5	4 N/A					
NONSTRUCTURAL INTERIOR 'WALLS'								
Partitions (HC tile) Partitions (pre-cast panels)	N/A, T, F, 0-10 N/A, T, F, 0-10	0 5	N/A 2					
EXTERIOR ORNAMENTATION								
Parapets, cornices, and appendages	N/A, T, F, 0-10	0	0					



Company Name:San Bernadino CountyDate:September 19, 2023Building Name:303 W. 5th StreetJob Number:23005335.00

Street Address: 303 W. 5th Street Engineer: Craig Chamberlain, S.E.

San Bernadino, CA, USA 92401 PE Number/State: CA SE 4588

MODIFIED FEMA-310 WORKSHEET

Category	Range	Typical	Modifier
INTERIOR ORNAMENTATION			
Building contents and furnishings Ceiling systems	T, F, 0-10 T, F, 0-5	5 5	2 2
Light fixtures	T, F, 0-5	5	2
MECHANICAL AND ELECTRICAL SYSTEMS			
Mechanical and electrical equipment	T, F, 0-10	5	5
Piping and sprinklers	T, F, 0-5	2	2
Ducts	T, F, 0-5	2 -	2
Elevators	N/A, T, F, 0-5	2 _	2
HAZARDOUS EXPOSURES - MATERIALS			
No hazardous materials	N/A, T, F, 0-10	0 _	0
OCCUPANCY (TYPE: OFFICE)			
Interior Construction	-5-5	0 _	-3
SITE DEPENDENT CHARACTERISTICS			
UBC Soil Class	A - E	D	Unknown
Liquefaction Resilience	Low - High	Low	Moderate
Liquefaction Susceptibility	V. Low-V. High	_	High
Depth to Water Table (ft)	0-1000+	15	Unknown
Landslide Susceptibility	V. Low-V. High	Very Low _	Very Low



Company Name:San Bernadino CountyDate:September 19, 2023Building Name:303 W. 5th StreetJob Number:23005335.00

Street Address: 303 W. 5th Street Engineer: Craig Chamberlain, S.E.

San Bernadino, CA, USA 92401 PE Number/State: CA SE 4588

VULNERABILITY SUMMARY

Component Modifier Summary

Base Class 90% Fractile Loss at MMI=IX (% of Value):

27

Modifiers to Base Class Loss

Item	Group Modifier (% of Loss)	Sigma (% of Loss)
1. Occupancy type:	-3	1.0
2. Connections:	0	0.7
3. Walls:		
A. Exterior	-1	3.1
B. Interior	-3	1.8
4. Diaphragms:		
A. Floor(s)	-1	0.9
B. Roof	0	1.6
5. Ornamentation:		
A. Exterior	0	1.7
B. Interior	-3	1.6
6. Mechanical/electrical systems:	0	3.4
7. Unusual conditions:	0	2.4
8. Hazardous exposures:		
A. Tank and overhanging walls	0	1.7
B. Pounding and adjacent buildings	0	0.0
9. Site dependent hazards:		
A. Proximity of active fault	0	12.8
Total	-11	14.3

Modified Base Class 90% Fractile Loss at MMI=IX (% of Value):

24

Loss vs MMI

MMI	Loss to Facilities (90% Frac. Loss	(% of Value) Mean	
V	0	0	
VI	2	1	
VII	10	5	
VIII	17	9	
IX	24	14	
X	28	16	
XI	31	18	
XII	35	20	



Company Name:San Bernadino CountyDate:September 19, 2023Building Name:303 W. 5th StreetJob Number:23005335.00

Street Address: 303 W. 5th Street Engineer: Craig Chamberlain, S.E.

San Bernadino, CA, USA 92401 PE Number/State: CA SE 4588

RISK SUMMARY

Expected Loss Table

Probability of	MMI	Loss to	BI (months)		
Exceedance		PL	SUL	SEL	
50.0% in 30 years 43 year return period	VII	3	9	5	N/A
10.0% in 30 years 285 year return period	VIII-IX	14	22	12	N/A
2.0% in 30 years 1485 year return period	IX	77	77	77	N/A
10.0% in 50 years 475 year return period	VIII-IX	20	25	14	N/A
2.0% in 50 years 2475 year return period	IX-X	86	86	86	N/A

Event and Fault Table

Close and Significant Seismic Sources	Maximum Magnitude	Closest Distance (km)	Max. MMI	Max. SUL *	Max. SEL *	Maximum Business Interuption (months)	Percent Contribution **
San Jacinto;SBV	7.1	2.9	VIII-IX	20	11	N/A	14
San Jacinto;SBV+SJV	7.3	2.9	VIII-IX	20	11	N/A	9
San Jacinto;SBV+SJV+A+C	7.8	2.9	VIII-IX	21	12	N/A	9
San Jacinto (SB to C)	7.7	2.9	VIII-IX	21	12	N/A	6
San Jacinto;SBV+SJV+A	7.6	2.9	VIII-IX	21	12	N/A	3
San Jacinto;SBV+SJV+A+CC	7.8	2.9	VIII-IX	21	12	N/A	<1
San Jacinto;SBV+SJV+A+CC+B+SM***	7.9	2.9	VIII-IX	21	12	N/A	<1
San Jacinto;SBV+SJV+A+CC+B	7.8	2.9	VIII-IX	21	12	N/A	<1
California Gridded	7.0	5.0	VIII-IX	19	11	N/A	2
Imp Extensional Gridded, Char, Strike Slip	7.0	5.0	VIII-IX	19	11	N/A	<1
Imp Extensional Gridded, Char, Normal	7.0	5.0	VIII	18	10	N/A	<1
Imp Extensional Gridded, GR, Normal	7.0	5.0	VIII	18	10	N/A	<1
San Gorgornio Shear Gridded	7.6	5.0	VIII-IX	20	11	N/A	3
S. San Andreas;SM+NSB	7.4	7.1	VIII	18	10	N/A	4
S. San Andreas; NSB+SSB	7.2	7.1	VIII	17	10	N/A	4
S. San Andreas;SM+NSB+SSB	7.6	7.1	VIII	18	10	N/A	3

^{*} Losses to individual events are from shaking only.

Average Annual Loss (% of Repl. Cost): 0.354893 Return Period of Major Liquefaction/Landslide: 675 Years **Business Interruption Average Annual Loss (\$): 0**



^{**} Percent contributions are for the probabilistic 475 year return period risk.

^{***} Event causing highest loss (from shaking only)

Company Name:San Bernadino CountyDate:September 19, 2023Building Name:303 W. 5th StreetJob Number:23005335.00

Street Address: 303 W. 5th Street Engineer: Craig Chamberlain, S.E.

San Bernadino, CA, USA 92401 PE Number/State: CA SE 4588

DISCLAIMERS and OTHER INFORMATION

RESULTS DISCLAIMER

This report, and the analyses, estimates and conclusions are based on scientific data, mathematical and empirical models, and experience of engineers, geologist and geotechnical specialist, using the input specified by the software licensee. Actual losses experienced during any earthquake may differ substantially from these estimates. Neither Fugro Consultants, Inc., Degenkolb Engineers, nor any third party supplier of information to this software can be held liable for any inaccuracies in the results obtained by ST-RISK.

SPRINKLER DAMAGE

Substantial building facilities loss has occurred in recent large earthquakes due to fire sprinkler damage. The figures presented herein may not adequately account for these potential losses. If the modifier for sprinklers in the Mechanical and Electrical Systems section of the Modified FEMA-310 Worksheet was 3 or higher, or '?', a more detailed evaluation of potential sprinkler damage should be made and additional loss anticipated.

THIRD PARTY DATA

Much of the data in this report is derived from data provided by the California Geological Survey (CGS), the US Geological Survey (USGS), the Geological Survey of Canada (GSC), as well as other parties. Most of the original data received was modified to make compatible with ST-RISK. None of these parties can be held liable for any inaccuracies inherent in the data or inherent in the modifications.



Company Name: San Bernadino County September 19, 2023 Date: 303 W. 5th Street **Building Name:** Job Number: 23005335.00

Street Address: 303 W. 5th Street **Engineer:** Craig Chamberlain, S.E.

> San Bernadino, CA, USA 92401 PE Number/State: CA SE 4588

> > **GLOSSARY**

MMI Modified Mercalli Intensity - A measure of ground motion intensity based on human perception of

motion and observed structural damage.

PML Probable Maximum Loss - A measure of seismic risk expressed as a percentage of replacement loss.

> Due to inconsistencies between the definition PML in recent standards and previous widespread practice, ST-RISK no longer identifies a particular results as being the PML. Instead, decision makers should identify the result that corresponds to the specific definition of PML that they are using.

PL Probable Loss - For a given time interval, or return period, this is the amount of loss that a property is

expected to meet or exceed on an average basis. This combines the probability distribution of hazard

with the full damage distribution, representing the best overall assessment of risk.

SUL Scenario Upper Loss - The percentage monetary loss (damage/replacement cost x 100) that has a 10

percent chance of being exceeded given any defined ground shaking intensity.

SEL Scenario Expected Loss - The expected, or mean, percentage monetary loss (damage/replacement cost x

100) that is predicted given any defined ground shaking intensity.

Mean Loss The expected, or average, percentage monetary loss (damage/replacement cost x 100) that is predicted

for a given ground shaking level.

BI Business Interruption / Loss-of-Use - The number of months that the facility is out of operation.

Base Class Loss The percentage monetary loss for 90% fractile (damage/replacement cost x 100) assigned to a building

class that accounts for type of construction and important construction deficiencies.

Modified Base

Class Loss

The percentage monetary loss for 90% fractile assigned to a building class that accounts for the Base

Class Loss and location and minor construction deficiencies.

Probability of

Exceedance

The probability that the ground shaking level or damage level will be exceeded.

Event Causing Highest Loss

The highest level of intensity due only to shaking that is experienced when considering all earthquakes

given a median predicted shaking level.

Maximum

Considered

Earthquake (MCE)

Loss associated with a 2% in 50 year probability of exceedence.

Uniform Building

Code (UBC)

Loss associated with a 10% in 50 year probability of exceedence as defined by new building design

provisions found in the Uniform Building Code.

% Contribution

Percent contribution of fault or fault segment to the 475-year return period risk.





M1 – existing air – cooled chiller



M2 – existing air-cooled chiller roof curb mount



M3 – roof gas piping without roof support



M4 – existing hot water boiler



M5 – existing hot water boiler piping assembly



M6 – typical existing rooftop heat pump





M7 – typical heat pumps leaking condensate



M9 – existing duct furnace flue

M8 – typical roof caps needs reseal



M10 – existing air handler centrifugal fan



M11 – existing damper linkage



M12 – existing fresh air intake



M13 – disrepair control wiring



M14 – existing chiller pump



M15 – air handler motor



M17 – typical vav box thermostat



M16 – typical heat pump thermostat



M18 – Liebert unit thermostat






M19 – typical T-bar lay-in type diffuser



M21 – typical surface mount diffuser

M20 - typical surface mount type grill



P1 - roof drain without cover



P3 – typical existing plastic roof vent



P2 – damaged roof drain cover



P4 – existing metal roof vent



P5 – existing A.O. smith water heater



P7 – existing water meter



P6 – abandoned water heater in mechanical room



P8 – typical existing drinking fountain



P9 – typical existing time clock exhaust fan in private rest room



P10 – typical existing flush-tank type water closet in private restroom



P11 – typical lavatory in private restroom



P12 – existing cabinet and sink in breakroom



P13 – existing kitchen sink



P14 – existing sink disposal



P15 – typical existing lavatory assembly in main restroom

P16 – typical existing flush-valve water closet



P17 - typical existing flush-valve water closet



P19 – existing wall mount faucet in janitor closet



P18 - existing mop sink in janitor closet



P20 – existing fire riser







P22 – existing gas meter



P23 – existing fire sprinkler backflow preventer



E1 - SCE Utility Transformer 500KVA, 12KU - 480/277V #P5055246 with 8' x 10' Slab box @ Parking Lot



E2 - Main Switchboard "MSB"



E3 - MCC 3P600A, 3P, 3W 480V (1981) @ 2nd Floor Mezzanine



E4 - Panels HA, DLA and Transformer T1 @ Main Electrical Room



E5 - Panels LB, HB and LB2 @ 2ne Floor Telecomm/Electrical Room




E6 - Panel LA 3P225A, 120/208V, 3P, 4W @ 2nd Floor Stair Closet



E7 - Panel A 2P100A, 120/208V (1981) @ 2nd Floor Stair Closet



E8 - Panel X, 3P70AMCB, 120/208V, 3P, 4W (1981) @ 2nd Floor Telecomm Room



E10 - Open power outlet box without devices @ 2nd Floor Clerical Office



E11 - Typical communications and power receptacle outlets with mounting heights of 16" above finish floor on center of devices







E14 - Typical elevator equipment disconnect switch without auxiliary contacts for proposed elevator recall function (1981))

E13 - Single duplex receptacle on roof without GFCI protection



E15 - Corroded disconnect switch on roof serving the boiler (1981)

LIGHTING



E16 - Typical surface 1' x 4' fluorescent fixture at garage and utility rooms



E18 - Typical HID type surface fixture at awning



E17 - Typical cylinder fluorescent surface fixture at garage lobby



E19 - Typical 2'x 4' recessed fluorescent fixtures at offices



E20 - Typical corridor recessed 2'x 4' fluorescent fixture



E22 - Incandescent wall mounted fixture at roof





E21 - Typical parapet halogen type spot light fixture on roof



E23 - Typical exit illuminated signage along egress path



E24 - Typical light switch mounted at +48" above finish floor from center of device

E25 - Main Communication Backboard and MPOE @2nd Floor Telecomm/Electrical Room

SIGNALS



E26 - Communication MPDE @ 2nd Floor Telecomm/Electrical Room




E28 - Remote security cabinet @ 2nd Floor Stair Closet



E27 - Security Cabinet @ 2nd Floor Telecomm/Electrical Room



E29 - Secondary Communication Backboard @ $2^{\rm nd}$ Floor Telecomm Room



E30 - Telecom Backboard with Punchdown in 2^{nd} Floor Telecomm Room



E32 - Typical voice/data jacks utilizing CAT5E horizontal cabling



CONTROL CONTRO

E31 - Security Door Control Cabinet in 2nd Floor Telecomm Room



E33 - Main Fire Alarm Control Panel in 2nd Floor Telecomm/Electrical Room

E34 - Fire Alarm Horn/Strobe and Fire Alarm Pull Station

