

ADDENDUM NO. 3

West Fontana Channel - Banana to Hickory

April 02, 2026

Page 1 of 2

ADDENDUM NO. 3
West Fontana Channel - Banana to Hickory
WORK ORDER: F02612
AREA: Fontana Area
SYSTEM ID/ROAD NO.: 1-809-6B

~~**BIDS OPEN 11:00 AM, THURSDAY APRIL 02, 2026**~~
BIDS OPEN 11:00 AM, THURSDAY APRIL 09, 2026

By Email via ePro System

The bid opening will be publicly viewable via goto.com, details are available in the Notice to Bidders pages of the Project Special Provisions.

Question via Epro:

1. Please provide the Insurance requirements / limits for the Railroad Protective Insurance required from SCRRA/Metrolink.
[Please refer to https://metrolinktrains.com/about/agency/right-of-way/](https://metrolinktrains.com/about/agency/right-of-way/) and their FAQ section for the insurance requirements. As a reminder, these requirements will be paid through the Supplemental Work (SCRRA/Metrolink Flagging, Inspection, Insurance, and Temporary K-rail) item.
2. Our takeoff quantities are significantly different from the owner quantity for items 40 and 42. Can you confirm the owner's quantities?
[The quantities have been confirmed. There may be a difference, as the excavation for the structural items are included in the item and it.](#)
3. Referencing the Responses for questions 42 and 63 in Addendum 2, please confirm that the acceptance of using shotcrete for the existing spillway concrete at Banana Basin, the 1.5:1 Trap Channel Slopes and the Transition Slopes from Trap Channel to Vertical Wall Channel can be placed using Shotcrete with a minimum compressive strength of 4000 psi. Shotcrete mixes are designed with 3/8-inch aggregates and cannot be placed with aggregates larger than 1/2-inch. The question response reference 1-inch aggregates. Please confirm that the use of shotcrete can be placed with 4000 psi mixes using 3/8-inch aggregate.
[Using shotcrete can be placed with 4000 psi mixes using 3/8-inch aggregate is acceptable.](#)
4. The Engineer's response to bid question no. 28 noted the type 1 retaining wall on drawing no. P-10 is Case 2. However, the footing thickness dimensions provided on the profile view and the bid quantity for item no. 71 both correspond with Case 3. Please note Case 2 dimensions are significantly higher and accordingly the estimated quantity for bid item no. 71 would be significantly more. Please review and advise.
[Plan sheet P-10 have been revised per addendum #3. Please see Attachment #1: Revised Bid Tabulation P-4 to P-10 for an updated quantity.](#)
5. Please clarify if either of the cut-off walls at the bottom (5' deep) or top (2' deep) of the concrete lined soft bottom channel slopes as shown on Drawing P-13, Detail A are to be paid and measured as part of the concrete lined soft bottom channel quantities or shall be included with the cut-off walls.
[Yes, all cut-off walls are included in the cut-off wall bid item.](#)

ADDENDUM NO. 3

West Fontana Channel - Banana to Hickory

April 02, 2026

Page 2 of 2

6. Please clarify what work is associated with Bid item no. 100 Channel Wall Underdrain 2.5" Thru Wall Drain and Appurtenances. Please reference specific details and specifications
[Please see note 11 on Plan Sheet S2-002.](#)

7. Please verify if all concrete shown on Drawing P-13 Detail A is to be constructed of 4,000 psi concrete with 1" maximum gradation. If not, please clarify.
[Yes, detail constructed of 4,000 psi concrete having a maximum gradation of one \(1"\) maximum, unless otherwise agreed upon the contractor and District.](#)

8. Question 10 on addendum 2 states that no backing rock is required for CRSP, the profile on P-1 of addendum 2 plans still shows backing under CRSP. Can you confirm that this is incorrect and no CRSP will require backing?
[No backing is required under any CRSP. Please see the revised Plan Sheet P-1.](#)

Special Provisions Attachments:

Attachment #1: Revised Bid Tabulation P-4 to P-10

Plans Attachments:

Attachment #2: P-1, P-10, and P-13

The addition of these requirements shall be considered in concert with existing documents in preparation of bids. **THE BIDDER'S CERTIFICATION FOR THIS ADDENDUM NO. 3 SHALL BE SIGNED BY THE SAME PERSON WHO SIGNS THE PROPOSAL AND SHALL BE SUBMITTED WITH THE PROPOSAL. ANY proposal not accompanied by a signed BIDDER'S CERTIFICATION (below) acknowledging receipt of this Addendum No. 3 will NOT be accepted.**

Noel Castillo, Director
Department of Public Works

By: 

Andy Silao, P.E., Chief
Contracts Division

AS:mt

BIDDER'S CERTIFICATION:

By my signature hereunder, I acknowledge receipt of Addendum No. 3 and I fully understand the intent and detail of Addendum No. 3, which I have considered in my preparation of the attached proposal.

Bidder's Signature

Date

Note: The page containing the executed BIDDER'S CERTIFICATION (just this page), must be included with the proposal.