


# Pre-Renovation Asbestos and Lead Survey Report

Glen Helen Regional Park – Island Tower  
2555 Glen Helen Parkway  
San Bernardino, California 92407

September 12, 2023 | Terracon Project Number: LA237543

**Prepared for:**

County of San Bernardino  
San Bernardino, California



Nationwide  
[Terracon.com](https://www.terracon.com)

- Facilities
- Environmental
- Geotechnical
- Materials



1355 E. Cooley Dr. Suite C  
Colton, CA 92324  
P (909) 824-7311  
**Terracon.com**

September 12, 2023

County of San Bernardino CA  
385 North Arrowhead Avenue, 2<sup>nd</sup> Floor  
San Bernardino, California 92415

**Attn:** Mr. Robert Burton  
Project & Facilities Management Department  
Project Manager I  
P: (909) 387-5000  
E: Robert.Burton@pfm.sbcounty.com

**RE:** Pre-Demolition Asbestos and Lead Survey Report with Visual Mold Inspection  
Glen Helen Regional Park – Island Tower  
2555 Glen Helen Parkway  
Yucaipa, San Bernardino County, California 92407  
Terracon Project Number: LA237543

Dear Mr. Burton:

Terracon Consultants, Inc. (Terracon) is pleased to present the findings of the pre-demolition asbestos and lead inspection with visual mold inspection performed on September 1, 2023, at the above referenced Property. The inspection was conducted in general accordance with Terracon Proposal No. PLA237543, dated August 15, 2023 and revised on August 16, 2023.

Terracon appreciates the opportunity to provide this service to County of San Bernardino. If you have any questions regarding this report, please contact Mark Korte in our Laguna Hills, California office at 949.383.1977.

Sincerely,  
**Terracon Consultants, Inc.**

A handwritten signature in black ink, appearing to read 'Mark Korte', written over a large, light gray diagonal watermark that says 'NOT FOR BID'.

Mark Korte, CAC, CDPH Lead I/A  
Project Manager

A handwritten signature in black ink, appearing to read 'Chris Blake', written over a large, light gray diagonal watermark that says 'NOT FOR BID'.

Chris Blake, CAC  
Senior Project Manager

## Table of Contents

1.0	Introduction.....	1
2.0	Building Description .....	1
3.0	Field Activities.....	1
3.1	Visual Assessment.....	1
3.2	Physical Assessment.....	2
3.3	Sample Collection and Analysis .....	2
4.0	Regulatory Overview.....	3
5.0	Findings .....	5
6.0	General Comments .....	6

APPENDIX A	Asbestos and Lead Sample Summary
APPENDIX B	Laboratory Analytical Reports
APPENDIX C	Sample Location Drawings
APPENDIX D	Licenses and Certifications

## 1.0 Introduction

Terracon Consultants, Inc. (Terracon) conducted a pre-demolition asbestos and lead survey with visual mold inspection of the Island Tower Building located within Glen Helen Regional Park, located at 2555 Glen Helen Regional Parkway San Bernardino, San Bernardino County, California. The inspection and sampling activities were conducted on September 1, 2023, by a California Division of Occupational Safety and Health (DOSH) Certified Asbestos Consultant (CAC) and California Department of Public Health (CDPH) Lead Sampling Technician.

The inspection objective was to evaluate building materials for potential asbestos and lead content and conduct a visual mold inspection prior to the planned repair and remediation of water damaged areas of the subject facilities.

## 2.0 Building Description

The subject building is situated within the Glen Helen Regional Park. The Park Office building interior is approximately 1,200 square feet and contains an attached garage. The subject building is identified as the Island Tower. The building is approximately 4,000 square feet in size and consists of multiple stories. Interior finishes include drywall walls, and concrete flooring. The exterior is finished with wood siding and the roof is pitched and comprised of wood shingles. The land is improved with landscaping, concrete paved parking, and utilities.

## 3.0 Field Activities

The inspection was conducted September 1, 2023, by Mr. Alan Alonso, a DOSH CAC and CDPH Lead Sampling Technician. All pertinent certifications and licenses are attached in Appendix D. A summary of the field activities is described below.

### 3.1 Visual Assessment

#### **Asbestos**

Terracon began the sampling activities with a visual assessment, identification and inventory of all homogeneous areas of suspect asbestos-containing materials (ACM). A homogeneous area consists of building materials that appear similar throughout in terms of color and texture. The assessment included all accessible interior and exterior areas of the subject buildings. Building materials identified as glass (includes fiberglass), wood, metal, and plastic were not considered suspect ACM.

#### **Lead-Containing Materials**

Inspection activities began with visual observations of painted surfaces to identify unique materials and applications throughout the subject areas.

## 3.2 Physical Assessment

### Asbestos

A physical assessment of each homogeneous area of suspect ACM was conducted to determine the friability and condition of the material. A friable material is defined by the U.S. Environmental Protection Agency (EPA) as a material which can be crumbled, pulverized or reduced to powder by hand pressure when dry. Friability was determined via tactile assessment.

### Lead-Containing Materials

Lead paint chip samples were collected to comply with DOSH regulations (Title 8 CCR 1532.1 – Lead Exposure in Construction) for the proposed renovation activities. Suspect lead-containing materials were sampled to identify potential worker exposure and disposal restrictions.

## 3.3 Sample Collection and Analysis

### Asbestos

Based on results of the visual observation, bulk samples of suspect ACM were collected in general accordance with Asbestos Hazard Emergency Response Act (AHERA) sampling protocols. Random samples of suspect materials were collected in each homogeneous area. Suspect asbestos-containing materials were collected using wet methods, where applicable, to reduce the potential for fiber release. Samples were placed in sealable containers and labeled with unique sample numbers.

Terracon collected twenty-seven (27) samples from nine (9) homogeneous areas. Samples of suspect ACM were delivered under chain-of-custody protocol to SGS Forensic Laboratories (SGS) in Carson, California. SGS is a laboratory accredited by the National Voluntary Laboratory Accreditation Program (NVLAP) under the National Institute of Standards and Technology (NIST) for analysis by polarized light microscopy (PLM). The asbestos inspection sample summary can be found in Appendix A. Laboratory analytical reports are included in Appendix B. The sampling locations are provided in Appendix C.

### Lead-Containing Materials

Five (5) paint chip samples were collected for lead analysis. The samples were delivered under chain-of-custody to SGS in Carson, California. The paint samples were analyzed by Flame Atomic Absorption (Flame AA) in accordance with EPA Method 7000B. The lead inspection sample summary can be found in Appendix A. Laboratory analytical reports are included in Appendix B. The sampling locations are provided in Appendix C.

## 4.0 Regulatory Overview

### Asbestos

As a consequence of the health hazard from inhalation of asbestos fibers, a body of federal and state regulations has been developed. Federal regulations pertaining to asbestos are included in AHERA (US EPA 40 CFR 763); National Emission Standard for Hazardous Air Pollutants (NESHAP [EPA 40 CFR 61]); Occupational Safety & Health Administration (OSHA) Asbestos Standards (29 CFR 1910.1001 and 29 CFR 1926.1101), and the Asbestos School Hazard Abatement Reauthorization Act (ASHARA). Many states have additional requirements including state-specific licensing and certification. In California, these regulations include, but are not limited to: Cal/OSHA in Title 8, Sections 1529 and 5208 and the South Coast Air Quality Management District (SCAQMD) Rule 1403.

The federal asbestos NESHAP standard (40 CFR Part 61, Subpart M) regulates asbestos fiber emissions and asbestos waste disposal practices. NESHAP also requires the identification and classification of asbestos removal in the SCAQMD. Under NESHAP, ACMs are classified as either friable, Category I non-friable or Category II non-friable ACM.

Friable materials are those that, when dry, may be crumbled, pulverized, or reduced to powder by hand pressure. Category I non-friable ACM includes packings, gaskets, resilient floor coverings and asphalt roofing products containing more than 1% asbestos. Category II non-friable ACM are any materials other than Category I materials that contain more than 1% asbestos.

Friable ACM, along with Category I and Category II non-friable ACM, which is in poor condition and has become friable or which will be subjected to drilling, sanding, grinding, cutting, or abrading and which could be crushed or pulverized during anticipated renovation or demolition activities are considered regulated ACM (RACM). Building materials confirmed to be ACM through the collection of bulk sampling and subsequent laboratory analysis, or presumed ACM, must be removed prior to intentional disturbance during planned renovation/demolition activities. Asbestos abatement must be conducted by Cal/OSHA-accredited asbestos abatement contractors. Third-party air monitoring should be conducted during the abatement activities.

Cal/OSHA requires that only properly licensed and certified asbestos abatement contractors are allowed to remove ACM. As per NESHAP, all RACM shall be removed from a facility being demolished or renovated before any non-burning demolition or renovation begins that would break up, dislodge, or similarly disturb the material or preclude access to the material for subsequent removal. According to SCAQMD, if more than 100 square feet of any ACM is to be stripped, removed, dislodged, cut, drilled, or similarly disturbed, or for any demolition, the asbestos abatement contractor or facility owner must submit an Asbestos Notification of Demolition and Renovation form to SCAQMD along with the appropriate fees within at least ten (10) working days prior to the scheduled asbestos removal activity or demolition start date. Planned renovations that do not meet the definition of 'demolition or renovation of a facility' per SCAQMD and where no ACM exists do not require notification to SCAQMD.

The federal OSHA Asbestos standard for construction (29 CFR 1926.1101) and the Cal/OSHA asbestos standard for general industry and the construction industry (CCR Title 8, Sections 5208

and 1529, respectively) regulate workplace exposure to asbestos. Both the federal OSHA and Cal/OSHA standards require that employee exposure to airborne asbestos fibers be maintained below 0.1 asbestos fibers per cubic centimeter of air (0.1 f/cc) as an eight-hour time weighted average (TWA). The federal OSHA and Cal/OSHA standards classifies construction and maintenance activities which could disturb ACM and specifies work practices and precautions which employers must follow when engaging in each class of regulated work. However, workers who deliberately disturb any amount of asbestos should have pertinent training and wear proper personal protective equipment according to federal and state regulatory requirements (i.e., Cal/OSHA 8 CCR 1529 (g) (1) through (9) for Class I, II and III work).

Asbestos-containing construction materials (ACCM) is a term developed by Cal/OSHA out of concern for non-hazardous building materials used inside and outside a building that contain less than 1% asbestos. The definition of ACCM includes any manufactured building material that has more than one-tenth of 1% ( $>0.1\%$ ) asbestos content. The SCAQMD requires point counting of friable samples of ACM at concentrations of less than 10% to determine more accurately the content of asbestos and proper classification of the material for proper abatement and disposal requirements. Alternatively, materials may be presumed as ACMs. If the material is less than one tenth of 1%, the material is not regulated by the EPA however Cal/OSHA worker protection regulations apply if any asbestos is detected.

## Lead

The Resource Conservation and Recovery Act (RCRA) gave the EPA authority to regulate the waste status of demolition and renovation debris, including lead-containing materials. Specific notification and testing requirements must be addressed prior to transporting, treating, storing, or disposing of hazardous wastes. Lead containing wastes are considered hazardous waste under RCRA if Toxicity Characteristic Leaching Procedure (TCLP) results exceed 5 milligrams per liter (mg/L). EPA exempts from most RCRA requirements those generators whose combined hazardous waste generation is less than 100 kilograms (kg) per month.

Detectable lead quantities may constitute a lead dust hazard during renovation/demolition activities. Personnel performing renovation/demolition activities that may disturb painted components with concentrations of lead above the designated analytical detection limit should comply with all current OSHA regulations in order to minimize employee exposure. OSHA regulates construction activities that disturb lead-containing material regardless of the concentration. Currently, any proposed renovation/demolition is subject to the OSHA regulations (29 CFR 1926.62 – Lead Exposure in Construction).

In California, the lead standard was adopted by DOSH as Title 8 CCR, Section 1532.1 (Occupational Lead Poisoning Prevention Program). The California Department of Public Health also regulates accreditations, certifications and work practices for activities involving lead-containing materials under Title 17 CCR. The federal and DOSH regulations define specific training requirements, engineering controls and working practices for construction personnel subject to this standard. Occupational exposure to lead occurring in the course of construction work, including maintenance activities, painting, alteration and repairs is subject to the OSHA Lead Exposure in Construction standard.

Contractors and employers are required to comply with 29 CFR 1926.62 and Title 8 CCR 1532.1. Construction work covered by federal and DOSH standards includes any repair or renovation activities or other activities that disturb in-place lead-containing materials. Employers must assure that no employee will be exposed to lead at concentrations greater than 50 micrograms per cubic meter ( $\mu\text{g}/\text{m}^3$ ) averaged over an eight-hour period without adequate protection. The Federal and California OSHA Standards also establish an action level of 30  $\mu\text{g}/\text{m}^3$ , which if exceeded, triggers the requirement for medical monitoring.

## 5.0 Findings

**Based on the results of laboratory analysis, asbestos was detected in five (5) of the homogeneous areas sampled. The confirmed ACM are detailed in the table below:**

**TABLE I  
CONFIRMED ASBESTOS CONTAINING MATERIALS**

HA	Material Description	Material Location	Result	NESHAP Class	Condition	Square Feet
1	Wallboard with Joint Compound	Tower Level 1 – Rooms 1 & 2	Drywall – ND Joint Compound – 2% CH	RACM	Good	1,800
2	Wallboard with Joint Compound	Tower Level 1 – Add-on	Drywall – ND Joint Compound – 2% CH	RACM	Good	350
3	Wallboard with Joint Compound	Tower Levels 2 - 4	Drywall – ND Joint Compound – 2% CH	RACM	Good	800
4	Wallboard with Joint Compound	Tower Level 6	Drywall – ND Joint Compound – 2% CH	RACM	Good	350
5	Roofing Felt under Wood Shingles	Roof	55% CH	RACM	Good	2,800

CH - Chrysotile asbestos

Please refer to the Asbestos Sample Summary in Appendix A for a summary of all materials collected and sample locations. The asbestos lab results and chain of custody forms for the suspect asbestos samples can be found in Appendix B.

Should suspect materials other than those which were identified during this inspection be uncovered prior to or during the demolition, those materials should be assumed asbestos-containing until sampling and analysis can confirm or refute asbestos content.

### Lead

Based on the results of laboratory analysis, four (4) of the five (5) sampled paint samples contain lead above the laboratory limit of detection. Two samples were above the regulatory definition of lead-based paint of 5,000 parts per million (ppm) and are considered Lead-Based Paint.

The lead lab results and chain of custody forms for the suspect lead paint samples can be found in Appendix B.



## Visual Microbial Survey

Refer to Table II for a breakdown of observed water damage.

**TABLE II**  
**VISUAL MOLD SURVEY BREAKDOWN**

Room	Description
1 <sup>st</sup> Floor	Suspect fungal growth, water staining, and water damage on all ceiling components.
1 <sup>st</sup> Floor Add-on	Suspect fungal growth, water staining, and water damage on all ceiling components (ceiling collapse).
2 <sup>nd</sup> Floor	Suspect fungal growth, water staining, and water damage on all ceiling components. Water Damage (deterioration) observed along wall paneling of north, west, and south walls.
3 <sup>rd</sup> Floor	Suspect fungal growth, water staining, and water damage on all ceiling components. Water damage (deterioration) observed along wall paneling of all walls, stairs leading to 4 <sup>th</sup> Floor.
4 <sup>th</sup> Floor	Suspect fungal growth, water staining, and water damage on all ceiling components. Water damage (deterioration) observed along wall paneling of all walls, stairs leading to 5 <sup>th</sup> Floor, wood subfloor is deteriorating.
5 <sup>th</sup> Floor	No water damage observed.
6 <sup>th</sup> Floor	Suspect fungal growth, water staining, and water damage on all ceiling components. Water damage (deterioration) observed along wall paneling of all walls.
Exterior	Significant water damage to roof, wood deteriorating.

## 6.0 General Comments

This limited asbestos and lead inspection was conducted in a manner consistent with the level of care and skill ordinarily exercised by members of the profession currently practicing under similar conditions in the same locale. The results, findings, conclusions, and recommendations expressed in this report are based on conditions observed during our inspection. This report has been prepared on behalf of and exclusively for use by County of San Bernardino for specific application to their project as discussed. This report is not a biddable document.

NOT FOR BID

## **APPENDIX A**

### **ASBESTOS AND LEAD SAMPLE SUMMARY**

## APPENDIX A

**Glen Helen Tower**  
**2555 Glen Helen Parkway**  
**San Bernardino, San Bernardino County, California 92407**

### ASBESTOS SURVEY SAMPLE LOCATION SUMMARY

HA	Sample No.	Description	Sample Location	Result
1	WB1-01	Wallboard with Joint Compound	Tower Level 1 - Room 1	Drywall - ND Joint Compound - 2% CH
	WB1-02	Wallboard with Joint Compound	Tower Level 1 - Room 2	Drywall - ND Joint Compound - 2% CH
	WB1-03	Wallboard with Joint Compound	Tower Level 1 - Room 2	Drywall - ND Joint Compound - 2% CH
2	WB1-04	Wallboard with Joint Compound	Tower Level 1 - Add-on	Drywall - ND Joint Compound - 2% CH
	WB1-05	Wallboard with Joint Compound	Tower Level 1 - Add-on	Drywall - ND Joint Compound - 2% CH
	WB1-06	Wallboard with Joint Compound	Tower Level 1 - Add-on	Drywall - ND Joint Compound - 2% CH
3	WB1-07	Wallboard with Joint Compound	Tower Level 2 - Room 1	Drywall - ND Joint Compound - 2% CH
	WB1-08	Wallboard with Joint Compound	Tower Level 3 - Room 1	Drywall - ND Joint Compound - 2% CH
	WB1-09	Wallboard with Joint Compound	Tower Level 4 - Room 1	Drywall - ND Joint Compound - 2% CH
4	WB1-10	Wallboard with Joint Compound	Tower Level 6 Room	Drywall - ND Joint Compound - 2% CH
	WB1-11	Wallboard with Joint Compound	Tower Level 6 Room	ND
	WB1-12	Wallboard with Joint Compound	Tower Level 6 Room	Drywall - ND Joint Compound - 2% CH
5	RF5-13	Roofing Felt under Wood Shingles	Roof - Northwest	55% CH
	RF5-14	Roofing Felt under Wood Shingles	Roof - Northwest	55% CH
	RF5-15	Roofing Felt under Wood Shingles	Roof - Southwest	55% CH
6	MA5-16	Concrete Walls	Tower Level 1 - Room 2	ND
	MA5-17	Concrete Walls	Tower Level 2 - Room 1	ND
	MA5-18	Concrete Walls	Tower Level 4 - Room 1	ND
7	MA5-19	Concrete Slab	Tower Level 1 - Room 1	ND
	MA5-20	Concrete Slab	Tower Level 3 - Room 2	ND
	MA5-21	Concrete Slab	Tower Level 5 - Room 1	ND
8	MA5-22	Concrete Steps	North Stairs	ND
	MA5-23	Concrete Steps	North Stairs	ND
	MA5-24	Concrete Steps	South Stairs	ND
9	MS5-25	Moisture Barrier Paper	Exterior - North by Stairs	ND
	MS5-26	Moisture Barrier Paper	Exterior - North by Stairs	ND
	MS5-27	Moisture Barrier Paper	Exterior - North by Stairs	ND

**Legend:**  
 ND - None Detected  
 CH - Chrysotile

## APPENDIX A

**Glen Helen Tower**  
**2555 Glen Helen Parkway**  
**San Bernardino, San Bernardino County, California 92407**

### LEAD SURVEY SAMPLE SUMMARY

Sample No.	Description	Sample Location	Condition	Result (ppm)
PB-01	White Paint on Wallboard	Men's Restroom	Intact	80
PB-02	Red Paint on Metal	Men's Restroom	Intact	20,000
PB-03	Red Paint on Metal	Exterior Siding - North	Intact	11,000
PB-04	Gray Paint on Metal	Exterior Trim -North	Intact	880
PB-05	Brown Paint on Wood	Exterior Siding - South	Intact	<60

< - Below the Laboratory Limit of Detection

NOT FOR BID

**APPENDIX B**  
**LABORATORY ANALYTICAL REPORTS**



# Bulk Asbestos Analysis

(EPA Method 40CFR, Part 763, Appendix E to Subpart E and EPA 600/R-93-116, Visual Area Estimation)

NVLAP Lab Code: 101459-1

Terracon-Carson  
Danish Mansoor  
145 W. Walnut St.

Carson, CA 90248

Client ID: L1987  
Report Number: B351522  
Date Received: 09/05/23  
Date Analyzed: 09/07/23  
Date Printed: 09/08/23  
First Reported: 09/08/23

Job ID/Site: LA237543; County of SB Glen Helen Tower Demo, 2555 Glen Helen Pkway, San Bernardino, CA 92407

Date(s) Collected: 09/01/2023

SGSFL Job ID: L1987  
Total Samples Submitted: 27  
Total Samples Analyzed: 27

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
<b>WB4-1</b>	51688531						
Layer: Grey Drywall			ND				
Layer: Beige Joint Compound		Chrysotile	2 %				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (20 %)	Fibrous Glass (Trace)						
<b>WB4-2</b>	51688532						
Layer: Grey Drywall			ND				
Layer: Beige Joint Compound		Chrysotile	2 %				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (20 %)	Fibrous Glass (Trace)						
<b>WB4-3</b>	51688533						
Layer: Grey Drywall			ND				
Layer: Beige Joint Compound		Chrysotile	2 %				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (20 %)	Fibrous Glass (Trace)						
<b>WB4-4</b>	51688534						
Layer: Grey Drywall			ND				
Layer: Beige Joint Compound		Chrysotile	2 %				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (20 %)	Fibrous Glass (Trace)						
<b>WB4-5</b>	51688535						
Layer: Grey Drywall			ND				
Layer: Beige Joint Compound		Chrysotile	2 %				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (20 %)	Fibrous Glass (Trace)						

Client Name: Terracon-Carson

Report Number: B351522

Date Printed: 09/08/23

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
<b>WB4-6</b>	51688536						
Layer: Grey Drywall			ND				
Layer: Beige Joint Compound		Chrysotile	2 %				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (20 %)	Fibrous Glass (Trace)						
<b>WB4-7</b>	51688537						
Layer: Grey Drywall			ND				
Layer: Beige Joint Compound		Chrysotile	2 %				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (20 %)	Fibrous Glass (Trace)						
<b>WB4-8</b>	51688538						
Layer: Grey Drywall			ND				
Layer: Beige Joint Compound		Chrysotile	2 %				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (20 %)	Fibrous Glass (Trace)						
<b>WB4-9</b>	51688539						
Layer: Grey Drywall			ND				
Layer: Beige Joint Compound		Chrysotile	2 %				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (20 %)	Fibrous Glass (Trace)						
<b>WB4-10</b>	51688540						
Layer: Grey Drywall			ND				
Layer: Beige Joint Compound		Chrysotile	2 %				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (20 %)	Fibrous Glass (Trace)						
<b>WB4-11</b>	51688541						
Layer: Grey Drywall with Debris			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (20 %)							
<b>WB4-12</b>	51688542						
Layer: Grey Drywall			ND				
Layer: Off-White Joint Compound		Chrysotile	2 %				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (20 %)	Fibrous Glass (Trace)						

Client Name: Terracon-Carson

Report Number: B351522

Date Printed: 09/08/23

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
<b>RF5-13</b>	51688543						
Layer: Grey Fibrous Material		Chrysotile	55 %				
Total Composite Values of Fibrous Components:		<b>Asbestos (55%)</b>					
Cellulose (Trace)	Fibrous Glass (Trace)						
<b>RF5-14</b>	51688544						
Layer: Grey Fibrous Material		Chrysotile	55 %				
Total Composite Values of Fibrous Components:		<b>Asbestos (55%)</b>					
Cellulose (Trace)	Fibrous Glass (Trace)						
<b>RF5-15</b>	51688545						
Layer: Grey Fibrous Material		Chrysotile	55 %				
Total Composite Values of Fibrous Components:		<b>Asbestos (55%)</b>					
Cellulose (Trace)	Fibrous Glass (Trace)						
<b>MA5-16</b>	51688546						
Layer: Grey Cementitious Material			ND				
Total Composite Values of Fibrous Components:		<b>Asbestos (ND)</b>					
Cellulose (Trace)							
<b>MA5-17</b>	51688547						
Layer: Grey Cementitious Material			ND				
Total Composite Values of Fibrous Components:		<b>Asbestos (ND)</b>					
Cellulose (Trace)							
<b>MA5-18</b>	51688548						
Layer: Grey Cementitious Material			ND				
Total Composite Values of Fibrous Components:		<b>Asbestos (ND)</b>					
Cellulose (Trace)							
<b>MA5-19</b>	51688549						
Layer: Grey Cementitious Material			ND				
Total Composite Values of Fibrous Components:		<b>Asbestos (ND)</b>					
Cellulose (Trace)							
<b>MA5-20</b>	51688550						
Layer: Grey Cementitious Material			ND				
Total Composite Values of Fibrous Components:		<b>Asbestos (ND)</b>					
Cellulose (Trace)							
<b>MA5-21</b>	51688551						
Layer: Grey Cementitious Material			ND				
Total Composite Values of Fibrous Components:		<b>Asbestos (ND)</b>					
Cellulose (Trace)							
<b>MA5-22</b>	51688552						
Layer: Grey Cementitious Material			ND				
Total Composite Values of Fibrous Components:		<b>Asbestos (ND)</b>					
Cellulose (Trace)							




Client Name: Terracon-Carson

Report Number: B351522

Date Printed: 09/08/23

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
<b>MA5-23</b>	51688553						
Layer: Grey Cementitious Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
<b>MA5-24</b>	51688554						
Layer: Grey Cementitious Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
<b>MS5-25</b>	51688555						
Layer: Paint			ND				
Layer: Grey/Tan Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (90 %)							
<b>MS5-26</b>	51688556						
Layer: Paint			ND				
Layer: Grey/Tan Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (90 %)							
<b>MS5-27</b>	51688557						
Layer: Paint			ND				
Layer: Grey/Tan Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (90 %)							



Tiffani Ludd, Laboratory Supervisor, Carson Laboratory

Note: Limit of Quantification ('LOQ') = 1%. 'Trace' denotes the presence of asbestos below the LOQ. 'ND' = 'None Detected'.

Analytical results and reports are generated by SGS Forensic Laboratories (SGSFL) at the request of and for the exclusive use of the person or entity (client) named on such report. Results, reports or copies of same will not be released by SGSFL to any third party without prior written request from client. This report applies only to the sample(s) tested. Supporting laboratory documentation is available upon request. This report must not be reproduced except in full, unless approved by SGSFL. The client is solely responsible for the use and interpretation of test results and reports requested from SGSFL. This report must not be used by the client to claim product endorsement by NVLAP or any other agency of the U.S. Government. SGSFL is not able to assess the degree of hazard resulting from materials analyzed. SGS Forensic Laboratories reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified. All samples were received in acceptable condition unless otherwise noted.







# Metals Analysis of Paints

(AIHA-LAP, LLC Accreditation, Lab ID #101762)

Terracon-Carson  
Danish Mansoor  
145 W. Walnut St.  
  
Carson, CA 90248

Client ID: L1987  
Report Number: M253736  
Date Received: 09/05/23  
Date Analyzed: 09/08/23  
Date Printed: 09/08/23  
First Reported: 09/08/23

Job ID / Site: LA237543; County of SB Glen Helen Tower Demo, 2555 Glen Helen Pkwy  
Date(s) Collected: 09/01/2023

SGSFL Job ID: L1987  
Total Samples Submitted: 5  
Total Samples Analyzed: 5

Sample Number	Lab Number	Analyte	Result	Result Units	Reporting Limit*	Method Reference
1	LM255481	Pb	0.008	wt%	0.006	EPA 3050B/7000B
Comment:	Additional Result: 80 ppm					
2	LM255482	Pb	2.0	wt%	0.2	EPA 3050B/7000B
Comment:	Additional Result: 20000 ppm					
3	LM255483	Pb	1.1	wt%	0.2	EPA 3050B/7000B
Comment:	Additional Result: 11000 ppm					
4	LM255484	Pb	0.088	wt%	0.007	EPA 3050B/7000B
Comment:	Additional Result: 880 ppm					
5	LM255485	Pb	< 0.006	wt%	0.006	EPA 3050B/7000B
Comment:	Additional Result: < 60 ppm					

\* The Reporting Limit represents the lowest amount of analyte that the laboratory can confidently detect in the sample, and is not a regulatory level. The Units for the Reporting Limit are the same as the Units for the Final Results.

*Kevin Poon*

Kevin Poon, Laboratory Supervisor, Hayward Laboratory

Analytical results and reports are generated by SGS Forensic Laboratories at the request of and for the exclusive use of the person or entity (client) named on such report. Results, reports or copies of same will not be released by SGS Forensic Laboratories to any third party without prior written request from client. This report applies only to the sample(s) tested. Supporting laboratory documentation is available upon request. This report must not be reproduced except in full, unless approved by SGS Forensic Laboratories. The client is solely responsible for the use and interpretation of test results and reports requested from SGS Forensic Laboratories. SGS Forensic Laboratories is not able to assess the degree of hazard resulting from materials analyzed. SGS Forensic Laboratories reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified. Any modifications that have been made to referenced test methods are documented in SGS Forensic Laboratories' Standard Operating Procedures Manual. Sample results have not been blank corrected. Quality control and sample receipt condition were acceptable unless otherwise noted.

Note\* Sampling data used in this report was provided by the client as noted on the associated chain of custody form.

1421 Edinger Avenue, Suite C  
Edinger, California 92780

# Lead

## Chain of Custody

ProjectName:Gv...f7uf-S1::>.C.le"H&lt Tuw<-/ 1"1 \_ Address: -Z. SS GI '": 4elu, /kvvc.7 /G.v, &/nc.t)......, e..A 97!'-107

Project#: 1A-Z:7J> S 3      Sampled By: At.... J. Al....)-l      Sampling Date: See-fe....      01' -i..-01-1

Laboratory: ☐ EMSL/LA Testing ☐ EM Lab ☐ Other: \_\_\_\_\_ **Email Report to:** anish.Mansoor@Terracon.com & Mark.Korte@TelTacon.com  
☐ Mike.Benefield@Terracon.com & Denise.Wallen@Terracon.com

Turnaround Time: ☐ 3 Hour ☐ 6 Hour ☐ 24 Hour ☐ 48 Hour ☒ 72 Hour ☐ 1 Week  Other:

Analysis: (3" Paint Chips(% by weight and ppm) SW846-7000B/7420 **E4A** ☐ Air Sample NIOSH 7082 **E4A** ☐ Air Sample NIOSH 7303 **ICP**

☐ Wipes SW846-131 I/7000B/7420 **EAA** ☐ Wipes SW846-60 I08/C **ICP** ☐ TCLP ☒ TTLC ☐ STLC ☐ Paint Chips SW846-60 I0B/C **JCP**[illegible]

Ab--- J. Af o.,.,u

(n)nnni (lli1h(Gj

o<:i (ot / .,02..3

$\{?, -, \cdot, \text{oil}(\cdot, \cdot, -$

00-os

q', SQ

 $F \in$

NOT FOR BID


**APPENDIX C**  
**SAMPLE LOCATION DRAWINGS**

LEGEND


Asbestos Samples

Lead Samples


1<sup>st</sup> Floor



2<sup>nd</sup> Floor



Sample Location Drawing		Island Tower – 1 <sup>st</sup> and 2 <sup>nd</sup> Floors	Exhibit
Prepared for: County of San Bernardino Project: Pre-Demolition Asbestos and Lead Survey Scale: Not to Scale Terracon Project Number: LA237543		Glen Helen Regional Park – Island Tower 2555 Glen Helen Parkway San Bernardino, California 92407	1



Sample Location Drawing

Prepared for: County of San Bernardino  
Project: Pre-Demolition Asbestos and Lead Survey  
Scale: Not to Scale  
Terracon Project Number: LA237543



Island Tower – 3<sup>rd</sup> – 6<sup>th</sup> Floors

Glen Helen Regional Park – Island Tower  
2555 Glen Helen Parkway  
San Bernardino, California 92407

Exhibit

2



# LEGEND

Asbestos Samples

Lead Samples



Sample Location Drawing

**Prepared for:** County of San Bernardino  
**Project:** Pre-Demolition Asbestos and Lead Survey  
**Scale:** Not to Scale  
**Terracon Project Number:** LA237543



Island Tower – Exterior / Roof

Glen Helen Regional Park – Island Tower  
2555 Glen Helen Parkway  
San Bernardino, California 92407

Exhibit

3

NOT FOR BID

## APPENDIX D LICENSES AND CERTIFICATIONS



State of California  
Division of Occupational Safety and Health  
**Certified Asbestos Consultant**



Alan J. Aloaso  
Name

Certification No. 22 7064

Expires on 01/05/24

This certification was issued by the Division of Occupational Safety and Health and authorized by Sections 1460 et seq. of the Labor Code and Professions Code.



California Department of  
**Public Health**

STATE OF CALIFORNIA  
DEPARTMENT OF PUBLIC HEALTH



## LEAD-RELATED CONSTRUCTION CERTIFICATE

INDIVIDUAL:



Alan Alonso

CERTIFICATE TYPE:

Lead Sampling Technician

NUMBER:

LRC-00004034

EXPIRATION DATE:

12/6/2023

Disclaimer: This document alone should not be relied upon to confirm certification status. Compare the individual's photo and name to another valid form of government issued photo identification. Verify the individual's certification status by searching for Lead-Related Construction Professionals at [www.cdph.ca.gov/programs/clnph](http://www.cdph.ca.gov/programs/clnph) or calling (800) 597-LEAD