

CONTRACTOR NOTES - SEWER

1. PRIOR TO INITIATING WORK ON OR ABOVE THE EXISTING SEWER LINE, THE CONTRACTOR SHALL MEET WITH REPRESENTATIVES OF THE CRESTLINE SANITATION DISTRICT (DISTRICT) TO DISCUSS THE WORK AND REVIEW PROCEDURES FOR DISTRICT SUPPLIED WORK AND INSPECTION OF THE CONTRACTOR'S WORK. CONTACT CRESTLINE SANITATION DISTRICT AT (909) 338-1751. IN ADDITION, THE CONTRACTOR SHALL CONTACT THE COUNTY OF SAN BERNARDINO ((909) 387-7910) TO ACQUIRE AN ENCROACHMENT PERMIT FOR THE WORK IN SAN MORITZ DRIVE.
2. UNDER THE SUPERVISION OF DISTRICT REPRESENTATIVES, THE CONTRACTOR SHALL EXPOSE THE EXISTING POINT OF CONNECTION ON THE SEWER LINE, OBSERVE AND RECORD THE SIZE OF THE MAIN, THE PIPE MATERIAL AND THE HORIZONTAL AND VERTICAL LOCATION AND REPORT THIS INFORMATION TO THE ENGINEER OF RECORD. THE CONTRACTOR SHALL ALLOW UP TO 10 WORKING DAYS FOR ENGINEER OF RECORD TO REVIEW THE FIELD DATA AND ADJUST THE DESIGN, AS NECESSARY. THE CONTRACTOR SHALL NOT BE ALLOWED OR PROVIDED WITH ADDITIONAL FUNDS FOR THE 10 DAYS REVIEW PERIOD AND MINOR MODIFICATIONS TO THE DESIGN.
3. IF IT IS DETERMINED THE PROPOSED CONNECTION POINT IS ACCEPTABLE, DISTRICT PERSONNEL WILL CONSTRUCT A NEW POINT OF CONNECTION USING A ROMAC "CB" STYLE SEWER SADDLE. THE CONTRACTOR WILL THEN INSTALL THE REMAINING PORTION OF THE PROPOSED 4-INCH SEWER LATERAL AND CONSTRUCT A 4-INCH CLEAN OUTS AS REQUIRED BY THE APPROVED LATERAL ALIGNMENT.
4. THE INSTALLATION PROCESS, INCLUDING EXCAVATION AND BACKFILL, BEDDING, AND ALL PIPE MATERIAL AND FITTINGS SHALL COMPLY WITH THE CRESTLINE SANITATION DISTRICT INFORMATION CONCERNING THE SANITARY SEWER SYSTEM.
5. THE CONTRACTOR IS RESPONSIBLE FOR ARRANGING ALL INSPECTIONS. CONTACT THE CRESTLINE SANITATION DISTRICT 24 HOURS IN ADVANCE AT (909) 338-1751 FOR INSPECTION.

SHEET INFORMATION:

STK PROJECT NO.: 374-178-23


SCALE: AS NOTED

DATE: DECEMBER 2023

PLOT DATE: -

DRAWING NAME:

SEAL:



SHEET TITLE:

DETAILS AND NOTES