

ADDENDUM NO. 2

**LAUREL AVENUE AT RANDALL AVENUE
WORK ORDER: H15101
AREA: FONTANA
ROAD NO.: 487800-0303, 688000-020**

**~~BIDS OPEN 10:00 AM, THURSDAY, SEPTEMBER 30, 2021~~
BIDS OPEN 10:00 AM, THURSDAY, OCTOBER 7, 2021**

By Email via ePro System

Amend the Special Provisions as follows:

1. Replace first paragraph to section 10-1.24 Fast-Setting Concrete (Minor Structure Slab), page SP-72 to read as follows:

Fast-setting concrete shall conform to provisions in Section 41, "Existing Concrete Pavement," and Section 90, "Concrete," of the Standard Specifications and these special provisions.

2. Add to section 10-1.24 – Fast Setting Concrete (Minor Structure Slab), page SP-73, after the ninth paragraph to read as follows:

WORK PLAN – The Contractor shall submit a work plan for the Fast Setting Concrete improvements. The Work Plan shall detail the removal of concrete, placement of dowels and bonding agents, epoxy, forming of the cross-gutter, curb, concrete panels and shifting traffic control. The work plan needs to detail how many laborers, masons, operators, etc. needed to perform these improvements. Also the plan shall address how many days needed to perform the work as the road shall stay open and no detours/closures are allowed.

3. Add to section 10-1.24 Fast Setting Concrete (Minor Structure Slab), page SP-73 after the tenth paragraph to read as follows:

TEST SECTION – The Contractor shall perform a trial slab on the southern section of Laurel Avenue. The test section shall include the removal of the existing concrete panel, installation of dowels, concrete and all other the other items of work included in Section 41, "Existing Concrete Pavement" and as stated within this section. Once the section is approved by the Engineer, the Contractor can proceed with the remainder of the fast-setting concrete work as shown in these plans and specifications.

4. Replace section 10-1.24 – Fast Setting Concrete (Minor Structure Slab), page SP-73, after the twenty-third paragraph to read as follows:

*Full compensation for furnishing & placing all bar reinforcing steel including dowels, epoxy, bonding agents and structure excavation & backfill for the above mentioned project concrete structure shall be considered as included in the contract price paid per cubic yard for **Fast setting Minor Concrete (Minor Structure Slab)** and no separate payment will be allowed therefore.*

The addition of these requirements shall be considered in concert with existing documents in preparation of bids. **THE BIDDER'S CERTIFICATION FOR THIS ADDENDUM NO. 2 SHALL BE SIGNED BY THE SAME PERSON WHO SIGNS THE PROPOSAL AND SHALL BE SUBMITTED WITH THE PROPOSAL. ANY proposal not accompanied by a signed BIDDER'S CERTIFICATION (below) acknowledging receipt of this Addendum No. 2 will NOT be accepted.**

BRENDON BIGGS, Director
Department of Public Works

By: 

Andy Silao, P.E., Chief
Contracts Division

AS:mb

BIDDER'S CERTIFICATION:

By my signature hereunder, I acknowledge receipt of Addendum No. 2 and I fully understand the intent and detail of Addendum No. 2, which I have considered in my preparation of the attached proposal.

Bidder's Signature

Date

Note: The page containing the executed BIDDER'S CERTIFICATION (just this page), must be included with the proposal.